

Darlington County Watershed Study Final Report

Darlington County, South Carolina

Prepared for:

South Carolina Office of Resilience
632 Rosewood Drive
Columbia, South Carolina 29201

Prepared by:

E. L. ROBINSON ENGINEERING
1301 Gervais Street, Suite 450
Columbia, South Carolina 29201
www.elrobinson.com



March 2023

TABLE OF CONTENTS

SECTION 1. INTRODUCTION

- A. Overview
- B. Known historic flooding issues within the County

SECTION 2. STUDY BACKGROUND

- A. Project goals and objectives
- B. Coordination with stakeholders, applicable agencies and organizations
- C. Design criteria
- D. Level of service definitions
- E. Other Grant Opportunities

SECTION 3. INDIVIDUAL PROJECT AREAS

- A. Comprehensive list of all projects considered
- B. Alternative selection criteria
- C. Project prioritization matrix and scoring
- D. Recommended project list, including level of service improvements
- E. Anticipated permitting requirements for each project
- F. Estimated project costs

SECTION 4. BENEFIT/COST ANALYSES AND LMI ASSESSEMENTS

- A. Qualitative and quantitative impact statement upon a LMI population for each project
- B. List of potentially impacted properties

SECTION 5. PROJECT ASSESSMENTS AND CONCEPT PLANS

- A. List of potential buyout properties
- B. A risk assessment of each project
- C. general exhibit of the proposed projects
- D. Detailed concept plans (approximately 10%)

APPENDICES

- A. Field Survey
- B. Precipitation Data
- C. Hydrologic Parameters Example
- D. PCSWMM Output
 - a. Moses Drive Area
 - i. Proposed Conditions - 10-year
 - b. Chestnut Street Area
 - i. Proposed Conditions - 10-year
 - c. M. L. King Drive Area
 - i. Proposed Conditions - 10-year
- E. 10% Concept Plans and Profiles

PLEASE NOTE: Contact SCOR Mitigation at mitigation@scor.sc.gov for questions regarding redacted information.

E.L. ROBINSON ENGINEERING

1301 Gervais Street, Suite 450
Columbia, SC 29201

SECTION 1. INTRODUCTION

A. Overview

Darlington County, South Carolina was awarded a U. S. Housing and Urban Development (HUD) Community Development Block Grant – Mitigation (CDBG-MIT) Program through the South Carolina Office of Resilience (SCOR). The grant was to fund a watershed study throughout the county that identifies and addresses the existing and future flooding concerns and issues and develops an implementation strategy for these individual, flood mitigating projects. These conceptual, proposed projects will be considered as part of a grant to develop plans and specifications for construction.

The study also included the municipalities of Darlington, Hartsville, Lamar and Society Hill and as well as the unincorporated areas. The projects areas that were selected for conceptual design were determined from several factors including: Low-and-Moderate Income (LMI), the number of affected residents, and socio-economic variables and potential benefits derived from the conceptual design when compared to estimated construction costs. A benefit-cost analysis will be used as the means to determine the feasibility of the projects, as well as comparison to competing projects in other counties of the state to obtain construction grants.

For Darlington County, four project areas were selected. These included:

- Moses Drive area south of the City of Darlington
- Chestnut Street area inside the City of Darlington
- M L King Drive south of the City of Hartsville
- Sampit Drive area southwest of Lake Robinson

The Sampit Drive area project will be completed after the submission deadline for 2023 of this round of construction projects.

This report documents the findings of the alternative analysis design phase of the project. The alternative analysis consisted of an existing conditions hydrologic/hydraulic (H&H) model and subsequent alternative conceptual designs and associate H&H models to alleviate the flooding problems. Levels of service of each drainage system will be determined for existing conditions and conceptual designs. A level of service is the capacity of the drainage system to drain the stormwater without flooding out of the system.

South Carolina has experienced three disasters that were presidential declarations. Hurricanes Joaquin, Matthew and Florence in 2015, 2016, and 2018, respectively. Most of the damages were a result of extreme rainfall over the area. Many of the communities affected were designated Low to Moderate Income (LMI) areas. Homes that were destroyed by flooding resulted in the homeowners moving out of the area and affecting nearby businesses and the local economy. These impacted

communities needed federal assistance in rebuilding and a stable future from extreme flooding events.

In 2018, HUD notified the State of South Carolina that it would receive an allocation of CDBG-MIT funds, for the specific purpose of mitigation activities in the Most Impacted and Distressed (MID) counties from the 2015 Severe Storm disaster and the Most Impacted and Distressed counties from the 2016 Hurricane Matthew disaster. The study included the inherent academic Social Vulnerability Index (SoVI) considerations associated with Low and - Moderate Income (LMI) communities.


The MID counties included Berkeley, Calhoun, Charleston, Chesterfield, Clarendon, Darlington, Dillon, Dorchester, Florence, Georgetown, Horry, Lee, Darlington, Orangeburg, Sumter, and Williamsburg.

Governor McMaster has by executive order established the South Carolina Floodwater Commission to identify a comprehensive solution and coordinate mitigation efforts because of flooding. The Commission will work to provide solution-based discussions and to identify and implement short-term and long-term recommendations to alleviate and mitigate flood impacts to this State, with emphasis on the coastal and river-based communities.

The SC General Assembly in Bill S.259 created the Office of Resilience in 2020. The legislation was enacted as the “Disaster Relief and Resilience Act” and created the S.C. Office of Resilience. The Office is tasked with developing, implementing, and maintaining the Statewide Resilience Plan with a goal of coordinating statewide resilience and disaster recovery efforts with the federal, state, local and non-governmental entities. The legislation also establishes the South Carolina Disaster Relief and Resilience Reserve Fund that will be used to maintain the Statewide Resilience Plan and for disaster relief assistance, hazard mitigation, and infrastructure improvements.


B. Known Historic Flooding Issues Within the County

Darlington County has had flooding throughout the county over many years. Once a mostly rural, farm-oriented area with ditches draining the agricultural fields, has now increased urbanization in many of the towns. These ditches were originally an irrigation system for low-lying agricultural fields. However, as the County developed and transitioned from agricultural to dense urban uses, the County no longer relied on agricultural lands and the irrigation systems were rendered obsolete but the many of the ditches were repurposed and used for stormwater management.



The main conveyance systems in many of the towns within the County were comprised of these ditches. These are still used today with ancillary stormwater systems connecting to these ditches. Most of the significant flooding areas are located within urban settings. These include the


Cities of Darlington and Hartsville. These systems were created without using significant engineering principles. This has created a system that does not convey stormwater during less frequency flooding events.



Social Vulnerability

Social vulnerability examines the socioeconomic and demographic character of places and helps to explain the variation in the population's ability to prepare for and respond to hazards. The Social Vulnerability Index (SoVI) is a statistical measure that compares social vulnerability to environmental hazards among places, and then visually displays these comparisons on a map. SoVI thus illustrates where there is uneven capacity for preparedness and response and where additional planning and response resources might be used most effectively to help residents. The variables used in determining the Social Vulnerability (SoVI) score along with how SoVI is calculated are available on the Hazards and Vulnerability Research Institute.

Within Darlington County, most of the census tracts exhibit moderate levels of social vulnerability. *The exceptions are Census tracts in Darlington (city) and in Hartsville, which have high SoVI scores and elevated levels of social vulnerability (see figure below).*



SECTION 2. STUDY BACKGROUND

A. Project Goals and Objectives

The overall project goals and objectives were to provide a comprehensive study that includes conceptual plans, provides levels of service for proposed stormwater conveyance system, and determines the benefit/costs of potential projects. of the county to include input from residents for

B. Coordination with Stakeholders, Regulatory Agencies and Organizations

Coordination with stakeholders included meeting with residents and any affected businesses from flooding events based on questionnaires and field visits. The agencies contacted included SCDOT, SCDHEC, US Corps of Engineers. The City of Darlington's and City of Hartsville's public works and other city departments were contacted. Based on the

C. Design Criteria

The design criteria were taken from SCDOT Requirements of Hydraulic Design Studies Manual, May 2009. In general, the area appears to have local drainage issues. The proposed project will improve conditions but will not fix all the existing drainage issues. The Level of Service relates the classification of the passage of stormwater through the system to a particular flood frequency. In our case, the Level of Service target was the 10-year 24-hour storm event.

Travel lane widths may be 9 feet to 11 feet depending upon the road group type. For rural roads, provide a minimum 4-foot shoulder or a 6-foot shoulder for Group 4 roads. The shoulder width includes a minimum paved width of 2 feet. Where bicycles are to be accommodated on the shoulder, the designer should provide a minimum paved shoulder width of 4 feet.

In constrained urban areas with low speeds, the shoulder width may be just the 3-foot valley gutter width. The use of curb and gutter and valley gutter sections are common on urban streets to reduce right-of-way requirements.

For specific lane and shoulder width criteria for local roads and streets, see the geometric design tables in Section 14.3.

Freeboard for Road Subgrades - To protect the pavement, it is recommended that road subgrades be 1.0 foot above the design high-water level.

Crossline Pipes - The design discharge for all crossline pipes for primary roads (SC or US designation) and interstate routes is the 50-year peak discharge. For secondary roads, the design discharge for crossline pipes is the 25-year peak discharge. The designer should analyze the 100-year or overtopping flood, whichever is less. This analysis does not change the design criteria.

Storm Drains and Roadside Ditches - The design storm for storm drain systems and roadside ditches is the 10-year storm for drainage areas from 0 to 40 acres, the 25-year storm for drainage areas from 40 to 500 acres, and the 50-year storm for drainage areas greater than 500 acres.

Inlet Spacing - Inlet spacing will be based on the spread criteria in the AASHTO Model Drainage Manual as modified below. For Type 16, 17, and 18 inlets, refer to the Department’s website for spacing charts. Recommended maximum spacing is 900 feet and recommended minimum spacing is 150 feet unless specified by the hydraulic design engineer. A 100-foot spacing will be used at sag points to flank the low point in the roadway.

Inlets in grassed medians will be spaced so that the 10-year stormwater level in the median will be below the edge of the shoulder. The maximum inlet spacing will be 750 feet.

Minimum Ditch and Pipe Grades - Minimum grade on ditches, gutters, and pipes in a storm drainage system is recommended to be 0.3 percent where possible. The recommended minimum velocity for the design discharge in a pipe should be 3.0 feet per second. This will promote self-cleaning of the pipe. The controlling factor is velocity rather than grade.

Minimum Pipe Size - Minimum pipe size in storm drainage systems and for crosslines is 18 inches. A 15-inch pipe may be used to connect yard drains to a storm drainage system and for driveway pipes.

Minimum Cover for Pipes - Consideration should be given to the type of inlet or manhole into which the pipe is connecting. For minimum cover requirements refer to SCDOT’s Standard Drawings for Road Construction.

The ditch sections and cross pipes could not meet the SCDOT design standards so a waiver may be required from the SCDOT.

Hydrological Criteria

Rainfall and Design Storm Events

Twenty four-hour point rainfall values from the NOAA Atlas 14 (Appendix B) were used in each analysis. This data is available on the web and is an interactive site. The rainfall values are summarized below. The Moses Drive Area and Chestnut St Area used the City of Darlington values. The M. L. King St area used the values from City of Hartsville.

| Location | Average Recurrence Interval, years (24-hr Duration) | | | | | | |
|--------------------|---|-------|-------|-------|--------|--------|---------|
| | 2-yr | 10-yr | 25-yr | 50-yr | 100-yr | 500-yr | 1000-yr |
| City of Darlington | 3.54 | 5.39 | 6.72 | 7.89 | 9.23 | 13.1 | 15.1 |
| City of Hartsville | 3.52 | 5.35 | 6.67 | 7.84 | 9.17 | 13.0 | 15.1 |

D. Level of Service

I. Purpose

Most of the stormwater conveyance systems within Darlington County are owned and operated by the S.C. Department of Transportation (SCDOT). The general class of roadways is primary and secondary with primary status given to the larger more traveled routes, i.e., interstates and US highways.

Darlington County only owns, operates, and maintains stormwater conveyance systems (e.g., pipes, ditches, and inlets) on local roads. The level of service for no surge in systems is the 10-year event. However, the designed systems keep flooding out of the drainage systems from the 25-year and beyond in some instances.

In general, the County only owns, operates, and maintains the stormwater system within County right-of-way, properly dedicated easements, or on County-owned property. The County desires to operate and maintain these systems in as efficient a manner as possible.

A Level of Service is a measure of service quality for a particular activity that defines the frequency and type of action desired to maintain operation of the stormwater conveyance system at an acceptable level. The physical assets owned, operated, and maintained by the County for the purpose of storing, conveying, or treating stormwater runoff include pipes, culverts, ditches, inlets and junction boxes, and stormwater control measures.

It should be noted that regardless of the established goals, there will always be circumstances that impact the County's ability to achieve the stated goal. Large storm events, economic downturns, loss of critical County staff, etc. all play a part in the County's ability to achieve a particular goal. The intent of each LOS is to provide direction for the program, assist in budgeting and business planning, and to create a common understanding of program expectations for staff, County leadership, and citizens.

E. OTHER GRANT OPPORTUNITIES

1. FEDERAL GRANT FUNDING SOURCES

US ENVIRONMENTAL PROTECTION AGENCY - Funding is available through the agency's Water Infrastructure Finance and Innovation Act (WIFIA) program and the State Infrastructure Financing Authority (SWIFIA) program. Letters of interest may be submitted and received by EPA any time.

US DEPARTMENT OF INTERIOR – FY23 WaterSMART Environmental Water Resources Projects. Water conservation & efficiency projects that result in quantifiable & sustained water savings & benefit ecological values; water management or infrastructure improvements to mitigate drought-related impacts to ecological values; & watershed management.

EPA Clean Water Act Nonpoint Source Grant (Section 319 Grants)—Congress amended the Clean Water Act in 1987 to establish EPA's Section 319 Nonpoint Source Management Program to provide greater federal leadership in focusing state and local nonpoint source efforts. Under Section 319, states, territories, and Indian tribes receive grant money to support a wide variety of activities, including:

- technical and financial assistance,
- education and training,
- technology transfer,
- demonstration projects, and

- monitoring to assess the success of projects implemented under the grant.

EPA Clean Water State Revolving Fund (CWSRF)—The CWSRF program is a federal-state partnership that provides communities a permanent, independent source of low-cost financing for a wide range of water quality infrastructure projects, including stormwater and green infrastructure.

EPA Environmental Justice Small Grants Program—The Environmental Justice Small Grants Program supports and empowers communities working on solutions to local environmental and public health issues. The program is designed to help communities understand and address exposure to multiple environmental harms and risks. Environmental Justice Small Grants fund projects up to \$30,000, depending on the availability of funds in a given year.

EPA Office of Sustainable Communities Greening America's Communities Program—Greening America's Communities is an EPA program to help cities and towns develop an implementable vision of environmentally friendly neighborhoods that incorporate innovative green infrastructure and other sustainable design strategies. EPA provides design assistance to help support sustainable communities that protect the environment, economy, and public health and to inspire local and state leaders to expand this work elsewhere.

EPA Office of Sustainable Communities Building Blocks Program—Building Blocks for Sustainable Communities provides quick, targeted technical assistance to selected communities using a variety of tools that have demonstrated results and widespread application. The purpose of delivering these tools is to stimulate a discussion about growth and development and strengthen local capacity to implement sustainable approaches.

FEMA Building Resilient Infrastructure and Communities (BRIC) program—This program supports states, local communities, tribes and territories as they undertake hazard mitigation projects, reducing the risks they face from disasters and natural hazards.

US Department of Agriculture - Rural Development Water and Environmental Programs (drainage, water, sewer, solid waste). The Rural Utilities Service, through its Water and Environmental Programs, provides financial assistance to eligible public bodies, Indian Tribes and non-profit organizations to construct, enlarge, or improve water, wastewater and solid waste disposal systems in rural areas.


US Department of Commerce - Economic Development Administration - Public Works (publicly owned infrastructure and facilities). Empowers distressed communities to revitalize, expand and upgrade their physical infrastructure to attract new industry, encourage business expansion, diversify local economies, and generate or retain long-term, private sector jobs and investment. All projects are evaluated to determine the extent to which they align with EDA's investment priorities, create or retain high-quality jobs, leverage public and private resources, demonstrate the ability to start the proposed project promptly and use funds quickly and effectively, and provide a clear scope of work and specific, measurable outcomes.

SOUTH CAROLINA INFRASTRUCTURE FUNDING SOURCES

South Carolina Rural Infrastructure Authority (SCRIA)

Grants are offered to assist in the development of reliable infrastructure statewide and increase capacity for economic growth. Financial assistance is made available during two competitive funding rounds annually. Applications are reviewed on a comparative basis with consideration of the relative need, feasibility and impact of each project. Funding decisions are made by the SCRIA's Board of Directors. RIA staff can provide technical assistance to help communities apply for funding to address critical infrastructure needs.

For FY 23 SCRIA will make its state grant dollars primarily available to assist with the SCIIIP local investment requirement. Utilities that serve 10,000 people or less may request up to \$500,000 of SCRIA state grant funds to be used towards their SCIIIP local investment requirement. Such a request may be made using the SCIIIP application form.



If available state funds are not fully obligated for SC Infrastructure Investment Program (SCIIIP) projects, RIA may consider applications for Emergency or Economic Infrastructure Jobs projects or Regional Feasibility Planning Grants. You may use the FY22 Fall round application for any

FY23 Emergencies or Economic/Jobs projects. See below.

Basic Infrastructure/Emergencies Grants

The Basic Infrastructure program is designed to assist communities in complying with environmental quality standards, protecting public health from other environmental concerns or *improving the capacity of existing infrastructure*. Funds may also be used to address infrastructure that has exceeded its useful life and no longer provides quality services.

Projects that require an urgent response to resolve a documented emergency may be submitted at any time for Tier 3 & 4 counties. Consider the following when trying to determine if the project meets the definition of an emergency need: the situation is an imminent threat to the health or environment, urgent or immediate action is required, and finally, no other resources are available to address the situation.

Economic Infrastructure/Jobs Grants

Through the Economic Infrastructure program, funding will help build or enhance local infrastructure to support economic development that will create and retain jobs as well as boost opportunities for future economic impact. Reliable infrastructure benefits both new and existing businesses and puts

1. Regional Solutions - Projects that implement solutions that impact multiple systems
 2. Water Quality - Projects that address consent orders, violations or other public health or environmental impacts
 3. Resilience and storm protection - Projects that help utilities prepare for emergencies
 4. Other aging infrastructure - Projects that upgrade or replace infrastructure that has exceeded its useful life
 5. Capacity - Projects that improve service for existing residents while preparing for future opportunities
- communities in a position to attract additional investment that will contribute to long-term community sustainability.

SC Infrastructure Investment Program (SCIIP)

The SCIIP is funded by the American Rescue Plan and administered by SCRIA.

The federal American Rescue Plan Act of 2021 (ARPA) directed Coronavirus Fiscal Recovery Funds to both state and local governments as part of a larger effort to combat the effects of the COVID-19 pandemic, including public health and economic impacts. ARPA identifies investments in water, wastewater and stormwater infrastructure as eligible uses of the fiscal recovery funds. In May 2022, the SC General Assembly allocated \$900M of these funds to the SC Rural Infrastructure Authority (RIA) for distribution primarily through a competitive grant process.

This funding offers a unique opportunity to make long-term capital improvements that will strengthen critical services to residents and businesses across the state, create more resilient communities and build the capacity to support economic and growth opportunities for the future.

Priority consideration will be given to projects based on a comparative analysis in the following relative order of need:

The deadline to submit a SCIIP grant application is now closed.

The federal expenditure deadline is December 31, 2026.

SC Department of Commerce - Community Development Block Grant Program (CDBG) (water, sewer, drainage, public facilities)- The CDBG Program provides grants for a wide variety of projects from revitalizing neighborhoods to improving community infrastructure, providing public facilities and creating or retaining jobs. The program targets low-to-moderate income areas.

SC Department of Health and Environmental Control (DHEC) - State Revolving Funds (SRF)

Clean Water SRF(sewer, stormwater) Drinking Water SRF. Both SRF programs provide long-term, low-interest loans. The Clean Water SRF finances all types of sewer facilities including treatment plants, collection systems, stormwater improvements for environmental and growth needs, and line relocation for road widening up to 30 years at 1.0% to 2.2%.

SECTION 3. INDIVIDUAL PROJECT AREAS

A comprehensive list of all projects considered was developed based on a matrix scoring criteria using the Low-to-Moderate Income area and/or Urgent Need criteria.

A. Comprehensive List of All Projects Considered

Flooding Locations with City of Darlington address.

The image shows two vertical columns of redacted data. Each column consists of a series of horizontal bars of varying lengths, representing rows of information that has been obscured by black boxes. The redaction covers the entire content of both columns.

Flooding Locations with City of Florence address.

The image shows a single row of redacted data, consisting of a horizontal bar of black boxes that obscures the information. The redaction covers the entire content of this row.

B. Project Prioritization and Matrix and Scoring

Darlington County/City projects considered based on LMI and/Urgent Need.

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent | Darlington Priority Ranking (L-Low, M-Mod., H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|--------------------|--|----------------------|---------------|---|------------------|------------------------------|------|
| [REDACTED] | SCDOT maintenance issue. Roadside ditches and culverts need cleaning. Resident says flooding occurs east of his home along S. Center Rd. Driveway and cross culvert need to be cleaned. | Maintenance | LMI | L | 77 | 115 / 2 | 55 |
| [REDACTED] | Flooding in the rear section of a subdivision. Homes are on a slab. Floods from resident's home to and along Lullwater Drive. Approx. 10+ homes. Photos texted. Need further investigation. Flood could be from design. | Design | LMI | M | 76 | 109/4 | 51 |
| [REDACTED] | SCDOT maintenance issue. Roadside ditches and driveway culverts and cross culvert need cleaning. Resident says flooding occurs because of clogged d/s ditch . Resident says cleaning needed. | Maintenance | LMI | M | 71 | 114/3 | 76 |
| [REDACTED] | SCDOT maintenance issue. Roadside ditches and driveway culverts and cross culvert need cleaning. Resident says flooding occurs because of clogged d/s ditch . Resident says cleaning needed. | Maintenance | LMI | M | 71 | 114/3 | 76 |
| [REDACTED] | SCDOT maintenance issue. Roadside ditches and driveway culverts and cross culvert need cleaning. Resident says flooding occurs because of clogged d/s ditch . Resident says cleaning needed. | Maintenance | LMI | M | 71 | 114/3 | 76 |
| [REDACTED] | This area is known as "Black Bottom" per the resident. There has been widespread flooding in the subdivision with water lasting for days before receding. This area might qualify for assistance. | Buyout / Design | LMI | H | 66 | 114/3 | 76 |
| [REDACTED] | The yard is low and acts as a bowl. There is a little ditch in the wooded area in front yard but doesn't appear to have any flow, maybe a field ditch from a long time ago. No contributing water observed, just a low area with no outlet. | Maintenance | LMI | L | 68 | 114/3 | 76 |
| [REDACTED] | Icoe Lane acts as a ditch itself draining all the surrounding farmland. There are no field ditches along the road so water has to run down the road to the cross pipe at washout. Large ditch in front of 525 is heavily vegetated and adding to the flooding situation. At a minimum there should be a ditch cut along the field to keep the road from washing out, then maintenance of the ditches. However, this is privately owned land and roads. | Design / Maintenance | LMI | M | 42 | 112/1 | 53 |
| [REDACTED] | Same as above | Design / Maintenance | LMI | M | 42 | 112/1 | 53 |
| [REDACTED] | Yard is very low and acts as a bowl with the edges of the yard higher than the interior. No way for water to drain off until it ponds high enough. Lot slopes from roadway towards the house. 24" rcp underneath the road at property line is 50% silted in and has standing water in the ditch. Was told neighbors have same issues. | Maintenance | LMI | M | 77 | 115 / 2 | 55 |


| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent | Darlington Priority Ranking (L-Low, M-Mod., H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|---|--|--------------------|---------------|---|------------------|------------------------------|------|
| [REDACTED] | Area is low all around her house, woods line, across the street and at the end of the street. Water appears to run down Flynn and fan out at the end of the road in her yard and across the street. No ditching is present. Area at woods line drops off into the woods so it seems the water would drain into the woods, unless the woods are flooded in these rain events preventing runoff into them. Maybe adding gutter or ditches. | Design | LMI | L to M | 60 | 112/2 | 53 |
| Chestnut Street between South Main Street and Dargan Street | Road is flat and has a low point near his house. There is a drainage system at the low point with inlets on both side in asphalt curbing. Drainage system may be clogged and/or undersized. Water noticed standing in one inlet at corner of Chestnut and Dargan with the outlet pipe submerged and 50% sited in. | Design/Maintenance | LMI | L to M | 54 | 114/2 | 74 |
| Chestnut Street between South Main Street and Dargan Street | Information in spreadsheet alluded to same conem as Winfred Herrington. | Maintenance | LMI | M | 54 | 114/2 | 74 |
| [REDACTED] | 875 Indian Branch - yard is low and bowl shaped. Evidence of ponding water seen in multiple places in yard, especially front right area. No roadway ditches present. Appears to collect water from 1074 West McIver and maybe other properties. Low area with nowhere to go. | Design/Maintenance | LMI | L | 59 | 112/4 | 54 |
| [REDACTED] | Investigated site. Large ditch behind trucking company appeared to have been recently cleaned out. Banks were mowed and no observed debris was in the ditch the entire length. Piles of debris were seen on the land adjacent to the ditch that could have possibly been removed from the ditch. Auction Ave was used to investigate the ditch. | Maintenance | LMI | L | 62 | 114/3 | 76 |
| [REDACTED] | The home is located at the end of the street. The yard is low and low around the shed as well. Road ditch was observed flowing towards his house in the field. The road ditch has no outlet at the end and appears should be flowing to the large ditch in the opposite direction. A regrade towards the large ditch would be recommended. There is a smaller ditch in the tree line along the property line but does not appear to carry any water, yard is lower than top of bank. | Design/Maintenance | LMI | M | 64 | 114/3 | 76 |
| [REDACTED] | Yard is flat and drains towards the back of the house. Ditch and pipe was found in the woods but pipe was underneath lots of debris and was not uncovered. Ditch seemed to be functioning, pipe should be cleaned out. | Maintenance | LMI | L | 57 | 114/2 | 74 |
| [REDACTED] | Yard is low and flat. No ditching along the road, drainage system is very deep and doesn't appear to capture much roadway runoff. The house has a pronounced drip line from the roof which is causing water to accumulate around the house due to no gutter system. Does not appear any offsite area is contributing to the flooding. | Design/Maintenance | LMI | L / M | 56 | 111/2 | 68 |

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent | Darlington Priority Ranking (L-Low, M-Mod., H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|--------------------------|--|---|---------------|---|------------------|------------------------------|------|
| | 36" rcp underneath the road has flowing water in the channel and evidence of roadway overtopping. Top of plastic pipe was found in outlet ditch, could not uncover but could be homemade pipe. Very silted in at the outlet ditch and soft sand. Water flowing into system must be traveling underground somewhere. Original ditch should be put back or at least homemade pipe dug up and sized correctly. Site appears to have a large DA and flooding a major issue for adjacent owners. | Design / Maintenance | Urgent Need | H | 40 | 110/2 | 39 |
| | Ditch along roadway relatively clean, drive pipes half silted in but not too bad. Rental house yards and vacant lot next to them are low and appear to trap water. Land from the ditch and woodsline slope to yard where it ponds. Area is low. | Maintenance | LMI | L | 67 | 114/3 | 76 |
| | Yard is low and appears lower than the ditches along the roadway. Ditch along road looks to have a high point/blockage before it ties to the large ditch towards 401 which could be causing water to back up. The rolled asphalt curb is supposed to drain to a DI on a cross pipe in a ditch behind his house. There is a low spot near his driveway where the water runs instead of flowing down. Local resident told property owner the road has sunken since it was built causing the low spot. Ditch running behind his house is silted in and DI's on both side of the road are blocked and need to be cleaned out. | Design / Maintenance | LMI | L / M | 39 | 112/1 | 53 |
| S. Main St @ E. Broad St | Area floods routinely with low area at Russell St and E. Broad St. and S. Main and E. Broad St. Drainage system needs redesign. | Design | LMI | H | 53 | 111/1 | 51 |
| Race Track Rd at bridge | Visited bridge. Water level was very high with possibly a beaver dam approximately 100' from upstream face. Water was close to low chord, bridge probably overtops regularly. | None | LMI | -- | 58 | 112/4 | 54 |
| | The pipe underneath the road is a 24" rcp that ties to a broken DI in valley ditch area. Pipe leaving the DI is a 15" terra cota pipe in very poor shape. The pipe has been dug up in two places and has a round hole cut into the top to act as an inlet to help with the standing water. At the outlet of the 15" the channel in very incised and had flowig water at the time of the visit. the outlet pipe has broken off and is very deteriorated. Sink holes are present in the back yard probably due to seperated pipe underground. Drainage system is undersized and in extremely poor condition. Area stays wet and exposed pipe and broken/damaged inlets are a hazard. | Design / Maintenance | Urgent Need | H | 47 | 114/4 | 29 |
| | There is a drainage system coming down road but no ditching to channel water into system. Her house is at the end of the line where all the water runs. Pipe in ditch at back property line is clogged. Water runs into her yard instead of down ditches. Entire area floods regularly. Top of DI beside driveway is broken and open and hazardous.. | Buyout / Design / Maintenance. Widesprea issue | LMI | H | 55 | 114/2 | 74 |

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent | Darlington Priority Ranking (L-Low, M-Mod., H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|--------------------|--|-------------------------------|---------------|---|------------------|------------------------------|------|
| ██████████ | Yard is flat and at an intersection. There are 2 DI's in the street in front of her house that have standing water in them. They connect to a drainage system in front of the school across the street from her. All the DI's have standing water in them and appear to be clogged. Could be blind JB's in this system that are clogged and a few DI's are damaged as well. | Maintenance | LMI | M | 57 | 114/2 | 74 |
| ██████████ | Yard is very low and acts as a bowl with the edges of the yard higher than the interior. Lot slopes from roadway towards the house and loop driveway acts like a dam holding water in the front yard and around the house. Roadway ditches look ok and drive pipes mostly clean. Septic system was being repaired during visit. Water has nowhere to go during heavy rains and sits around house and yard. Unsure if ditching would help. | Design / Maintenance | LMI | M | 28 | 109/2 | 54 |
| ██████████ | Her home is the last property before the ditch goes under Pineforest. Yard is very low on the right side and middle of property. 36" rcp under the road is 50% silted in and outlet ditch not very defined and is heavily wooded. Water appears to pond on upstream side and back up into her yard. Pipe needs to be cleaned out and outlet channel regraded to promote positive flow. | Buyout / Design / Maintenance | Urgent Need | H | 32 | 113/1 | 27 |
| ██████████ | Roadway ditches along both roads look ok, some growth but still functioning. Issue appears to be the outfall ditch adjacent to James Gibson's house and beyond. The ditch is heavily overgrown and looks to have a large drainage area. Resident claims a property owner downstream filled in the ditch to make a driveway which has backed up the water at these locations. An attempt was made to locate the blockage but could not pinpoint the actual location of the homeowner. Water has been in residents homes and garages multiple times and does not flow. | Design / Maintenance | LMI | H | | 109/2 | 54 |
| ██████████ | Site had no apparent flooding issues. Back of house is used for car storage and was a little muddy, no grass established. Land fell off behind house in wooded area, no surrounding properties appeared to have flooding issues. | Maintenance | LMI | L | 100 | 112/1 | 53 |
| ██████████ | Yard is flat and slopes from road towards home. Evidence of standing water in places around home. Could not assess condition underneath the house or settling. Road ditches are somewhat clean but should be cleaned out, drive pipes are 80% silted in. | Maintenance | LMI | M | 99 | 109/2 | 54 |
| ██████████ | Area around home and back yard is low and appears to have a bowl shape with the sides of the lot being higher than interior causing water to pond in heavy rains. Unable to determine where roadway ditches flow but do need cleaning out as well as drive pipes and cross culverts. | Maintenance | LMI | L / M | 71 | 114/3 | 76 |
| ██████████ | Home looks deserted. Area is low with a ditch across the street with standing water in it. Another resident very close by reported flooding issues across the road from this site. | Maintenance | LMI | M | 106 | 114/2 | 74 |

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent | Darlington Priority Ranking (L-Low, M-Mod., H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|--------------------|---|----------------------|---------------|---|------------------|------------------------------|------|
| ██████ | Streets do not have ditching or pipe networks, yard slopes towards house and house is lower than surrounding yard. | Maintenance | LMI | L / M | 55 | 114/2 | 74 |
| ██████ | Wooded area across the road was very wet, ditches full and stagnat water. The ditches should flow somewhere but do not. All neighbors in this area have similar complaints. Outlet should be identified where water should be draining, it could be along 52 near the Ford dealership but hard to determine. No existing ditches or pipes around this area. | Design / Maintenance | LMI | M / H | 106 | 114/2 | 74 |
| ██████ | Yard is low and house is lower than perimeter of the yard. Very large ditch in the back is overgrown and is the main outfall channel for what appears to be a large drainage area. Field and surrounding yards flood in major storm events. | Maintenance | LMI | M | 104 | 112/4 | 54 |

Flooding Locations with a City of Hartsville Address.




Flooding locations with a Town of McBee address.



| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent Need | Hartsville Priority Ranking (L-Low, M-Med, H-High) | Detailed Map No. | Census Tract and Block Group | LMI% |
|--|---|----------------------|--------------------|--|------------------|------------------------------|------|
| [REDACTED] | No visible outlet below (south) of John St. Ditch located north of John Street that flows eastward under Patrick Hwy was recently widened. This widened ditch ultimately flows under Antioch Rd and N. 5th St (US 15) into Black Creek. Property has flooded many times in the past prior to recent ditch widening. | Buyout / Design | Urgent Need | H | 9 | 103 BG4 | 46.1 |
| [REDACTED] | These locations are the same investigate for 1240 Patrick Hwy. | See 1240 Patrick Hwy | Urgent Need | H | -- | 103 BG4 | 46.1 |
| [REDACTED] | Drainage system needs replacing. Ditch behind residents along Kenwoods flood during heavy rainfall. Also, runoff from west side of Kenwood enters area also. Outfall of ditch to Sonoco Rd needs investigation to determine capacity. Resident's crawl space & HVAC gets damaged. | Buyout / Design | Urgent Need | H | 11 | 106 BG1 | 42.7 |
| [REDACTED] | Drainage system needs replacing. Ditch behind residents along Kenwoods flood during heavy rainfall. Also, runoff from west side of Kenwood enters area also. Outfall of ditch to Sonoco Rd needs investigation to determine capacity. | Design | Urgent Need | H | 11 | 106 BG1 | 42.7 |
| In front of Hartsville High School, Marlboro Ave, and Carolina Elementary School | Large Ditch system along Lewellen Ave needs cleaning and maintenance. Water backs up at clogged culvert at entrance to cemetery at sharp corner of road. | Maintenance | -- | H | 15 | 105 BG1 | 38.4 |
| [REDACTED] | Valley gutter section along roadway need to be larger and more inlets needed to intercept drainage flowing to low point at 626 6th St. | Design | LMI | M | 22 | 107 BG1 | 65.1 |
| Butler St | Drainage system needs to be designed and constructed on the east side of 8th Ave. for this entire area. | Design | LMI | H | 16 | 107 BG1 | 65.1 |
| [REDACTED] | | Maintenance | LMI | M | 16 | 107 BG2 | 76.3 |
| Carter Dr | | -- | LMI | M | | 107 BG2 | 76.3 |
| E. Chaplin Circle | | -- | LMI | M | | 107 BG1 | 65.1 |
| [REDACTED] | Side ditches needs trees removed and cleaned. | Maintenance | LMI | M | 20 | 107 BG2 | 76.3 |

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent Need | Hartsville Priority Ranking (L-Low, M-Med, H-High) | Detailed Map No. | Census Tract and Block Group | LMI % |
|---------------------------------------|--|----------------------|--------------------|--|------------------|------------------------------|-------|
| MLK Drive and Russell Road Properties | Ditches behind residents on MLK Blvd need to be cleaned and drainage system designed. Ditch that runs parallel to MLK Blvd needs to be graded to have positive flow toward Marion Ave. | Design | LMI | H | 21 | 107 BG2 | 76.3 |
| [REDACTED] | Ditches behind residents on MLK Blvd need to be cleaned and drainage system designed. Ditch that runs parallel to MLK Blvd needs to be graded to have positive flow toward Marion Ave. | Design | LMI | H | 21 | 107 BG2 | 76.3 |
| [REDACTED] | Ditches behind residents on MLK Blvd need to be cleaned and drainage system designed. Ditch that runs parallel to MLK Blvd needs to be graded to have positive flow toward Marion Ave. | Design | LMI | H | 21 | 107 BG2 | 76.3 |
| 1415 Martin Luther King Dr | Ditches behind residents on MLK Blvd need to be cleaned and drainage system designed. Ditch that runs parallel to MLK Blvd needs to be graded to have positive flow toward Marion Ave. | Design | LMI | H | 21 | 107 BG2 | 76.3 |
| [REDACTED] | Water flows from airport and floods across road during moderate rainfall. This is a safety hazard that needs immediate attention. Cross culvert under Whipoorwill Rd is too small. Downstream extension of culvert has collapsed or separated in several areas. This extension goes to back of parcel and discharges into woods and travels to Oak Hill Ct. Airport detention area may not be operating properly. | Design | Urgent Need | H | 4 | 102 BG2 | 25.5 |
| [REDACTED] | Ditches and culverts need to be cleaned. There could be an obstruction downstream causing the flooding. Home gets water underneath. | Design / Maintenance | LMI | H | | 106 BG2 | 60.9 |
| [REDACTED] | Large amount of runoff flows into this area. Much of it comes from Hwy 151 and the storage units. There does not appear to be an outlet and water ponds in homes and yards. Recommend Buyouts for those home that flood. | Design | Urgent Need | H | -- | 104 BG3 | 17.6 |
| [REDACTED] | Large amount of runoff flows into this area. Much of it comes from Hwy 151 and the storage units. There does not appear to be an outlet and water ponds in homes and yards. Recommend Buyouts for those home that flood. | Buyout / Design | Urgent Need | H | -- | 104 BG3 | 17.6 |
| [REDACTED] | No drainage system in neighborhood. Water ponds in yard during heavy rains and stays for hours. Residents are trapped because of flood waters. | Design | Urgent Need | H | 114a | 102 BG1 | 34.1 |
| [REDACTED] | No drainage system in neighborhood. Water ponds in yard during heavy rains and stays for hours. Residents are trapped because of flood waters. | Design | Urgent Need | H | 114a | 102 BG1 | 34.1 |
| [REDACTED] | No drainage system in neighborhood. Water ponds in yard during heavy rains and stays for hours. Residents are trapped because of flood waters. | Design | Urgent Need | H | 114a | 102 BG1 | 34.1 |

| Flooding Locations | Field Visit Assessment | Type of Solution | LMI or Urgent Need | Hartsville Priority Ranking (L-Low, M-Med, H-High) | Detailed Map No. | Census Tract and Block Group | LMI % |
|--------------------|---|------------------|--------------------|--|------------------|------------------------------|-------|
| | No visible outlet below (south) of John St. Ditch located north of John Street that flows eastward under Patrick Hwy was recently widened. This widened ditch ultimately flows under Antioch Rd and N. 5th St (US 15) into Black Creek. | Design | Urgent Need | H | | 103 BG4 | 46.1 |
| | No visible outlet below (south) of John St. Ditch located north of John Street that flows eastward under Patrick Hwy was recently widened. This widened ditch ultimately flows under Antioch Rd and N. 5th St (US 15) into Black Creek. | Design | Urgent Need | H | | 103 BG4 | 46.1 |
| | No visible outlet below (south) of John St. Ditch located north of John Street that flows eastward under Patrick Hwy was recently widened. This widened ditch ultimately flows under Antioch Rd and N. 5th St (US 15) into Black Creek. | Design | Urgent Need | H | | 103 BG4 | 46.1 |
| | No visible outlet below (south) of John St. Ditch located north of John Street that flows eastward under Patrick Hwy was recently widened. This widened ditch ultimately flows under Antioch Rd and N. 5th St (US 15) into Black Creek. | Buyout / Design | Urgent Need | H | | 103 BG4 | 46.1 |



C. ALTERNATIVE ANALYSES

The alternative analysis was carried out by creating several scenarios for each study area: Moses Drive, Chestnut Street and M. L. King Drive. Since these areas are nearly at buildout conditions, no future analysis was conducted. There were several ditches in each of the areas that could be converted to pipes but every effort was taken to keep as many ditches open to achieve “green” infrastructure improvements and water quality benefits. The ditches can be lined with a geo-fabric for long-term stabilization (resilient) and ease of maintenance. Pipes with limited slopes tend to clog if velocity is under 3 fps.

The alternative selection criteria were set by using the SCDOT criteria for secondary roads since many if not most roads in the County are owned and operated by the SCDOT. The ditches and culverts were sized to attempt to convey the 10-year storm event. The SCDOT criteria requires roadway cross pipes to convey the 25-year storm event. However, it would not be feasible to meet that criteria for MLK and Moses Drive areas. The storm-drain pipes and ditches were sized to try to keep the 10-year hydraulic grade line below the crown of the pipe or top of bank; however, this criteria were not met for each case. The system did not flood but was under surcharge effect. The storm drain system does not have capacity for storm events greater than the 10-year event. Designing system beyond the 10-year event would be too costly and require much more right-of-way.

The storm drain system was evaluated using the PCSWMM computer model updated in 2022. Structure losses were calculated using the HEC-22 Second Edition method. The storm drain system will convey both the runoff from the ditches as well as sheet flow from the proposed roadway.

The rain gardens and infiltration pond capacity were designed to hold and infiltrate the runoff from the 10-year proposed conditions so that the improvements would not adversely impact the downstream area.

The 2-, 10-, 25-, 50- and 100-year 24-hour storm events were used in the PCSWMM model to determine the effects of flooding. In all cases in each area, the existing systems could not pass the two event without flooding out of the system. Various scenarios were considered using engineering judgement, constructability and potential permitting requirements. For example, several sites within each study area had an existing ditch along a home or roadway to alleviate the concentrated flow in one pipe. The situation was reviewed to see if piping the ditch was a better method of conveying stormwater. While the piped system may operate sufficiently, it would be more expensive and provide less water quality. However, it could be more aesthetically pleasing to have the system piped between homes and provide a level of safety if small children are present.

Procedure

Each project area was divided into separate subcatchment to account for multiple discharge points into the drainage model. Subcatchment parameters were obtained from various sources that included the soil data captured from the NRCS Websoil Survey and Subcatchments were delineated within the

PCSWMM model using the contour elevations from the most recent LIDAR data. A contour layer was developed within PCSWMM to draw the subcatchments for each discharge point in the model. Using the export feature in the model, subcatchments were exported to shapefiles and then imported into Websoil survey website to obtain the exact area for each subcatchment. Composite curve numbers were developed for each subcatchment based on approximate percentages of each soil type and land use.

The time of concentration, Tc was measured from each subcatchment from the farthest point to the discharge point in the model. The slope was measured and used as part of the calculation of the Tc.

The SCS lag equation was used to compute Tc in the model for each subcatchment.

| | | |
|---|--|--|
| $Lag \text{ (hrs)} = L^{0.8}((1000/CN-10)+1)^{0.7}/1900Y^{0.5}$ | | |
| $Tc \text{ (min)} = Lag * 1.67 * 60$ | | |

The PCSWMM model has an option to allow the user to compute Tc by the SCS method. A spreadsheet was developed to calculate the composite CN, slope and Tc (as a check) for each subcatchment and is included in the appendix.

Two of the study areas (Moses and MLK) included only ditches and secondary road cross pipes for the drainage system. The Chestnut area was in an urban setting and had a closed drainage system. Nesbitt Surveying provided the data for pipes and ditches along with ELR surveyors. The inlets tops required assistance from the City of Darlington for the Chestnut Street Area. This was to lift off the tops because of the difficult access to get invert, size and type of the pipes.

The ditches and culverts were sized to attempt to convey the 10-year storm event. The SCDOT criteria requires roadway cross pipes to convey the 25-year storm event. However, it would not be feasible to meet that criteria for MLK and Moses Drive areas. The storm-drain pipes and ditches were sized to try to keep the 10-year hydraulic grade line below the crown of the pipe or top of bank; however, this criteria were not met for each case. The storm drain system does not have capacity for storm events greater than the 10-year event. It should be noted that the baseline design criteria were the 10-year event, lower frequency storm events (25-, 50-, and 100-year) safely passed through the proposed drainage system without significant flooding in all project areas.

The storm drain system was evaluated using the PCSWMM computer model updated in 2022. Structure losses were calculated using the HEC-22 Second Edition method. The storm drain system will convey both the runoff from the ditches as well as sheet flow from the proposed roadway.

The rain gardens and infiltration pond capacity were designed to hold and infiltrate the runoff from the 10-year proposed conditions so that the improvements would not adversely impact the downstream area.

D. Recommended Project List

The recommended project list was developed with the input from SCOR and the County. These were selected from the total list previously shown above. They were selected for conceptual design for submittal to FEMA for a follow-up construction grant.

They include:

- Moses Drive Area – Located just south of the City of Darlington
- Chestnut Street Area – Located within City Limits of Darlington
- ML King Drive Area – Located just south of the City of Hartsville
- Sampit Drive Area – (This study will be included in the next rounds of construction grant submittals next year (2024))

Level of Service

The results of the proposed conditions show a markedly improved drainage system. The proposed conceptual design safely passes a 10-yr design frequency storm for the achieved Level of Service. The conceptual design also reduces the peak flows and flooding for the less frequent storm events (25-,100-year design storms). PCSWMM output for the 10-year proposed scenario is shown in Appendix D.


The PCSWMM models are included in a separate zipped file along with other input data.



Moses Drive Area


Existing and Proposed Conditions



The Moses Drive Area consists of Moses, Ridgeway, Sandridge, Watercrest and Woodstream Drives. Major flooding was reported in this area. Woodstream Drive extends further south and dead ends near the creek. There is only one entrance to the Moses Drive area which adds to the emergency during a flood. There is no other evacuation route and emergency vehicles are hampered by the floodwaters. The existing conditions for the drainage system show that it floods even at the 2-year storm event.

Ditches sections are located on each side of the roads and receive sheet flow from property and the roadways. The existing system has inverted slopes though pipes and some ditches are perched. The field survey and PCSWMM model confirmed the two resident locations that were noted in the questionnaire forms as flooding had driveway culverts that were below the other inverts in the drainage system. This condition not only flooded those residents but also backed up the drainage system and flooded surrounding areas. There are two outfalls for the Moses Drive Chestnut Street Area. The east outfall discharges near the railroad tracks. The south outfall discharged toward the stream.











Chestnut Street Area

The Chestnut Street Area is an urban area in downtown Darlington. The drainage system is antiquated and consists of 12-inch to 30-inch RCPs in poor condition. Much of the drainage infrastructure is buried and several could not be located, particularly, just south of Chestnut street at the intersection with Southern Pines Street. This system had many inlets that were inaccessible and required the help of the City of Darlington Public Works Staff to assist in lifting the inlet grates and tops.

Drainage system layout is shown below for the Existing Conditions. PCSWMM output is in the Appendix for the 2-, and 10-year existing and proposed conditions.



The proposed conditions consisted of additional inlets and correcting inverted slopes for each drainage line. Pipe sizes were increased to pass the 2- and 10-year events. The results of these improvements can be seen in the Appendix. The 2- and 10-year profiles for the existing and conditions profiles are shown to see improvements in the hydraulic grade lines.




Bio-retention areas were developed along Chestnut Street to reduce flooding and allow stormwater to pond and infiltrate. Detention areas were also used to reduce peak flows downstream. These facilities were located near the outfalls.

The following figures show an example of the existing conditions from Node 20 to the Outfall (Node OF2) at South Main Street. Note this existing line cannot pass the 2-year storm event. The proposed condition nearly passes the 10-year events and allows stormwater to flow to the outfall more freely. The existing and proposed discharges for Outfall OF1 and OF2 were 6.74 cfs vs 2.7 cfs and 19.7 cfs vs. 10.1 cfs.

The downstream drainage segment was relocated behind the apartments on South Pine Road. The existing drainage system in that location is a 30-inch RCP that drains under the cul-de-sac (Court St) to the south and joins other pipes at the tree line at a junction box J38. The drainage line to the north of Court Street was rerouted to the east and toward S. Main Street where it joins a box (Outfall OF1) at S.

Main Street. The 30-inch line was opened as a channel to provide water quality and provide ease of maintenance. It also reduced the cost of material for construction. The pipes tend to clog over time due to the flat slope. Also, dual pipes were proposed from King Edwards Street to Allen Street along Southern Pines Street. The pipes are shown below in purple with the pipe name, size (in feet), and number of barrels shown in red. The northern outfall OF1 receives stormwater from the north part of Virgil Wells Circle. The system was disconnected from OF2 to provide relief for the southern segment.

Reduction in flooding can be seen in the profile figures below for Junction J11 to Outfall OF2. Street flooding is eliminated at Virgil Wells Circle, Chestnut Street and Southern Pines Street.




Legend



- Junctions
- ▲ Outfalls
- Conduits
- ARM Subcatchments





200 m



Junction J11 to Outfall OF2 (Existing) shown in purple.








M. L. King Drive



M. L. King Drive area has experienced severe flooding over time without any major assistance. This area has had a history of flooding. The main ditch that runs parallel to the MLK Drive and is the outfall for the system for the area at Russell Road and MLK Drive. Most of the flooding occurs nearer the intersection of Russell Road and MLK.



The existing conditions consist of very shallow ditches along the roads, especially along ML King Drive. During rainfall events, runoff sheet flows across the roadway and enter residents' yards and around homes. Residents that reported flooding during the public meeting phase of the project lived predominately on ML King Drive. ELR personnel met with residents to discuss their flooding issue and is documented in the Existing Conditions Report.



Flooding for existing conditions shows major street flooding along Russell Road and ML King Drive. Discharge to the outfall is very limited due to the flood storage in the roads and residents' lots. The figure below shows the proposed layout with improvements to all the ditches and many driveway and cross culverts. The bright green node shown represents 1.5 acres of detention storage that reduces to peak discharge for proposed conditions to the outfall. The intent of the design was to move water out of the roadway ditches as quickly as possible toward the outfall and detain the runoff in the detention area.



Columbia, SC 29201







E. Anticipated Permitting Requirements

The potential permitting requirements for the project will include those for several state and federal entities.

- *SC Department of Transportation (SCDOT)* – An encroachment permit that addresses ingress/egress into properties may be required.
- *SC Department of Health and Environmental Control (SCDHEC)*
 - NPDES - Sediment and Erosion Control
- *US Army Corps of Engineers (USACE)* - Section 401 (water quality) & Section 404 (Wetlands) will be needed.

US Fish & Wildlife Service– An Endangered Species Act (ESA) may be required.

SECTION 4. BENEFIT/COST ANALYSIS AND LMI ASSESSMENT


A. Qualitative and Quantitative Impact Statement Upon Low-and-Moderate Income Areas

Low-to-Moderate Income (LMI) Areas


The Moses Drive, Chestnut Street and ML King Drive Areas had LMI percentages of 76.36, 74.07 and 76.29, respectively.

This information was taken from the US Housing and Urban Development (USHUD) website and is based on the 2011-2015 American Community Survey. These data are to be used to qualify all new area-benefit activities as of April 1, 2019. *To qualify, the LMI area must have a value of 51% or greater with no rounding.*

Moses Drive Area LMI



Chestnut Street Area LMI




The Community Development Block Grant (CDBG) program requires that each CDBG funded activity must either principally benefit low- and moderate-income (LMI) persons, aid in the prevention or elimination of slums or blight or meet a community development need having a particular urgency. Most activities funded by the Community Development Block Grant (CDBG) program are designed to benefit low- and moderate-income (LMI) persons. This benefit may take the form of housing, jobs, and services.

The impacts the current condition of the drainage system has on the town is severe with moderate to heavy rainfall. Extreme rainfall events have impacted a high percentage of residents in these areas. The proposed conditions give relieve to these residents through the 25-year event. The system is designed to primarily convey stormwater through the system without surcharging most of the pipes and channels.

Flooding also impacts health and the environment. Much of the sewer system is impacted during flooding, whether a septic system or manhole overflows from a sewer system. Also treatment plants are affected by wet weather inflows into the system via infiltration.

ML King Drive LMI Area



B. Benefit – Cost Analysis

A Benefit – Cost Analysis (BCA) was developed for each project as part of the study to determine cost effectiveness. The results also are used to rank each project according to the BCA.

A Benefit – Cost Analysis (BCA) was developed for each project as part of the study to determine cost effectiveness. The results also are used to rank each project according to the BCA.

Damage data from taken from the Arizona State University’s Center for Emergency Management and Homeland Security - Spatial Hazard Events and Losses Database for the United States. The SHELDUS database was used to determine county-level hazard data. SHELDUS Version 21.0 was launched on February 15, 2023. The database covers the period from January 1960 to December 2021. SHELDUS covers natural hazards such thunderstorms, hurricanes, floods, wildfires, and tornados as well as perils such as flash floods, heavy rainfall, etc.

The database contains information on the date of an event, affected location (county and state) and the direct losses caused by the event (property and crop losses, injuries, and fatalities) as well as insured crop losses (indemnity payments by the U.S. Department of Agriculture). Insured crop losses cover the period from January 1989 to December 2021. The database contains loss information for Puerto Rico, Guam, and other U.S. territories from 2000 through 2021. SHELDUS is updated annually.

There are a number of hazards listed in the SHELDUS program. The hazard type used on our analyses was flooding.

Contact information:

Center for Emergency Management and Homeland Security
Arizona State University
411 N Central Ave
Mail Code 4020
Phoenix, AZ 85004

The BCA Analyses were computed using the FEMA BCA Toolkit Version 6.0.0 (01-02-23).

Benefit-Cost Ratio

The benefit-cost ratio (benefits divided by cost) is defined as the benefit divided by the estimated cost. This ratio is an expression of the money saved by implementing a project as opposed to the costs occurred by not implementing the project. A ratio less than one means the project will cost more to implement than it will save. Any ratio equal to 1 or higher justifies the project from a pure financial viewpoint.

The ratios are then sorted by quartile to award points when compared to competing projects. This will weaken the cost-benefit ratio defined by a single value to account for the larger picture of the project, account for error from assumptions and methodologies and be appropriate for the stage of most projects.

| <i>Benefit-Cost Ratio Quartile</i> | <i>Points</i> |
|---|----------------------|
| 0-25% | 0 |
| 25-50% | 7 |
| 50-75% | 13 |
| 75-100% | 20 |

The analyses yielded values show below.

Moses Drive Area – BCR = 5.84

Chestnut Street Area – BCR = 2.52

ML King Drive Area – BCR = 3.27



Benefit-Cost Calculator

V.6.0 (Build 20230103.1822 | Release Notes)

Benefit-Cost Analysis

Project Name: Moses Drive Area - Drainage Improvements



| Map Marker | Mitigation Title | Property Type | Hazard | Using 7% Discount Rate | | | Using 3% Discount Rate (For FY22 BRIC and FMA only) | | |
|-------------------------|--|---------------|----------------------|------------------------|---------------------|-------------|--|---------------------|-------------|
| | | | | Benefits (B) | Costs (C) | BCR (B/C) | Benefits (B) | Costs (C) | BCR (B/C) |
| ▲ | Drainage Improvement @ 34.3322968; -79.9576503 | | DFA - Riverine Flood | \$ 8,301,345 | \$ 1,420,841 | 5.84 | \$ 15,476,817 | \$ 1,778,712 | 8.70 |
| TOTAL (SELECTED) | | | | \$ 8,301,345 | \$ 1,420,841 | 5.84 | \$ 15,476,817 | \$ 1,778,712 | 8.70 |
| TOTAL | | | | \$ 8,301,345 | \$ 1,420,841 | 5.84 | \$ 15,476,817 | \$ 1,778,712 | 8.70 |



Benefit-Cost Calculator

V.6.0 (Build 20230103.1822 | Release Notes)

Benefit-Cost Analysis

Project Name: Chestnut Area - Drainage Improvement



| Map Marker | Mitigation Title | Property Type | Hazard | Using 7% Discount Rate | | | Using 3% Discount Rate (For FY22 BRIC and FMA only) | | |
|-------------------------|---|---------------|----------------------|------------------------|---------------------|-------------|--|---------------------|-------------|
| | | | | Benefits (B) | Costs (C) | BCR (B/C) | Benefits (B) | Costs (C) | BCR (B/C) |
| ▲ | Drainage Improvement @ Darlington, South Carolina | | DFA - Riverine Flood | \$ 6,576,718 | \$ 2,607,878 | 2.52 | \$ 12,261,466 | \$ 3,252,045 | 3.77 |
| TOTAL (SELECTED) | | | | \$ 6,576,718 | \$ 2,607,878 | 2.52 | \$ 12,261,466 | \$ 3,252,045 | 3.77 |
| TOTAL | | | | \$ 6,576,718 | \$ 2,607,878 | 2.52 | \$ 12,261,466 | \$ 3,252,045 | 3.77 |



Benefit-Cost Calculator

V.6.0 (Build 20230103.1822 | Release Notes)

Benefit-Cost Analysis

Project Name: MLK Area Drainage Improvements



| Map Marker ▲ | Mitigation Title | Property Type | Hazard | Using 7% Discount Rate | | | Using 3% Discount Rate (For FY22 BRIC and FMA only) | | |
|-------------------------|--|---------------|----------------------|------------------------|---------------------|-------------|--|---------------------|-------------|
| | | | | Benefits (B) | Costs (C) | BCR (B/C) | Benefits (B) | Costs (C) | BCR (B/C) |
| 1 | Drainage Improvement @ Darlington County, South Carolina | | DFA - Riverine Flood | \$ 4,509,484 | \$ 1,380,370 | 3.27 | \$ 8,407,368 | \$ 1,753,152 | 4.80 |
| TOTAL (SELECTED) | | | | \$ 4,509,484 | \$ 1,380,370 | 3.27 | \$ 8,407,368 | \$ 1,753,152 | 4.80 |
| TOTAL | | | | \$ 4,509,484 | \$ 1,380,370 | 3.27 | \$ 8,407,368 | \$ 1,753,152 | 4.80 |

SECTION 5. PROJECT ASSESSMENTS AND CONCEPT PLAN

Potential Property Buyout Locations

Based on these onsite assessments and investigations, the following properties are recommended for potential buyout locations.



Risk Assessment for Each Project

Flood impacts are the specific types of damage that could occur because of flooding. The flood impacts identified are the specific consequence that could result from the flood water. Not all impacts are directly related to property damage but have equally devastating consequences, such as the closing of a flooded street or the inability of a homeowner to leave a house surrounded by flood water.

Examples of flood impacts include flooding in the living space of a house, flooding of an outdoor heating or air conditioning unit, or damage to personal property such as a car. Flooding above the lowest floor of a building can cause varying levels of damage to a structure. Even a small amount of flood water inside a house for example can damage flooring and cabinets. Higher levels of flooding can cause serious damage to sheet rock, doors, and the building's electrical systems. Long-term flooding can also result in mold and mildew that can lead to serious health issues.

Assessment of the risk must consider the likelihood that a particular impact would occur. Storm event recurrence interval flood data will be used to estimate the frequency of occurrence of a flood impact. The estimated flood elevations are founded on a statistical analysis of the likelihood that a watershed

will receive enough rain over a certain period (24 hours) to produce storm water runoff sufficient to reach a flood level equal to or exceeding a certain elevation in any given year. An example of this concept is the “100-year storm event.” The 100-year storm event predicts in any given year there is a 1 percent chance that a watershed will receive enough rain to produce flood levels equal to or exceeding a specified level during a 24-hour time period. This concept is a useful tool in estimating the likelihood that a flood impact will occur. The recurrence interval is an annualized probability. There is a 1 percent chance that a 100-year storm will occur during 2023 and a 1 percent chance that a 100-year storm will occur in 2024 and so on. The storm event recurrence intervals that will be used to quantify the probability of flood impacts are listed below.

| Storm Event | Annual Exceedance Probability | Flood Risk |
|-------------|-------------------------------|---------------|
| 2-year | 50% | High |
| 10-year | 10% | Elevated |
| 25-year | 4% | Medium |
| 50-year | 2% | Low |
| 100-year | 1% | Extremely Low |

For our four (4) projects, the proposed Level of Service (LOS) was the 10-year storm event. This meant that the stormwater flowed freely within pipes, culverts and ditches without surcharging (pressurizing the pipes or culverts) or ditches overflowing. The proposed systems *did* pass the 25-year and occasionally, the 50-year event without flooding out of the system. All the existing projects could not pass the 2-year storm event. The risks for the existing conditions were considered high. Physical contact with flooding and other social vulnerability considerations can impact risk.

References

1. E. L. Robinson Engineering, *Hartsville Drainage Study*, 2021
2. E. L. Robinson Engineering, *Darlington County Watershed Study, Existing Conditions Report*, 2022
3. E. L. Robinson Engineering, *Darlington County Watershed Study, Alternative Analysis Report*, 2023
4. South Hartsville – Housing Affordability & Marketability Study, December 2016.
5. South Carolina Department of Transportation, *South Carolina Roadway Design Manual*, 2021.
6. USDA, NRCS, TR-55, Peak Flow Determination, 1986.
7. City of Greenville, Stormwater Levels of Service Policy, 2018.
8. Darlington County GIS data
9. South Carolina Floodwater Commission, *South Carolina Floodwater Commission Report*, November 2018
10. National Hurricane Center, Tropical Cyclone Report – *Hurricane Florence, 31 August to 17 September 2018*, September 2019
11. National Hurricane Center, Tropical Cyclone Report – *Hurricane Matthew, 28 September to 9 October 2016*, April 2017
12. US Department of Commerce, *The Historic South Carolina Floods of October 1-5, 2015*, July 2016.
13. National Hurricane Center, Tropical Cyclone Report – *Hurricane Joaquin, 28 September to 7 October 2015*, January 2016
14. US Geological Survey, *Flood Inundation Maps of Selected Areas Affected by the Flood of October 2015 in Central and Coastal South Carolina*, 2016
15. USGS, *Monitoring storm tide and flooding from Hurricane Matthew along the Atlantic coast of the United States*, October 2016
16. Federal Emergency Management Agency, *Flood Insurance Study for Darlington County, SC*, 2013
17. NOAA National Hurricane Center, *Hurricanes in History*, Webpage
18. Federal Emergency Management Agency, *Flood Insurance Study for Darlington County, SC*, 1991
19. Wilbur Smith Associates, *Analysis of the Flood of October 1990 – Black Creek Watershed, Chesterfield and Darlington Counties*, 1992
20. USGS, Preliminary peak stage and streamflow data selected Stream gaging Stations South Carolina
21. Darlington County webpage for questionnaire and flood mapping, GIS-based, OnPoint! Media
22. Flood Risk Assessment and Reduction Community Guidebook, U.S. Department of Homeland Security
23. Arizona State University’s Center for Emergency Management and Homeland Security - *Spatial Hazard Events and Losses Database for the United States*. February 2023.

Appendix A – Field Surveys

Moses Drive Area

Chestnut Street Area

ML King Drive Area

Appendix B – Precipitation Data



NOAA Atlas 14, Volume 2, Version 3
 Location name: Darlington, South Carolina, USA*
 Latitude: 34.2749°, Longitude: -79.8612°
 Elevation: 149.71 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnh, D. Martin, B. Lin, T. Parzybok, M.Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps_&_aerials](#)


PF tabular

| PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹ | | | | | | | | | | |
|--|-------------------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|-----------------------|----------------------|----------------------|
| Duration | Average recurrence interval (years) | | | | | | | | | |
| | 1 | 2 | 5 | 10 | 25 | 50 | 100 | 200 | 500 | 1000 |
| 5-min | 0.435 (0.400-0.472) | 0.507 (0.468-0.550) | 0.588 (0.541-0.638) | 0.659 (0.605-0.714) | 0.741 (0.677-0.802) | 0.807 (0.734-0.872) | 0.869 (0.787-0.939) | 0.929 (0.836-1.00) | 1.00 (0.896-1.09) | 1.07 (0.945-1.16) |
| 10-min | 0.694 (0.639-0.753) | 0.811 (0.748-0.880) | 0.942 (0.866-1.02) | 1.05 (0.967-1.14) | 1.18 (1.08-1.28) | 1.28 (1.17-1.39) | 1.38 (1.25-1.49) | 1.47 (1.33-1.59) | 1.59 (1.42-1.72) | 1.68 (1.49-1.82) |
| 15-min | 0.868 (0.799-0.942) | 1.02 (0.941-1.11) | 1.19 (1.10-1.29) | 1.33 (1.22-1.44) | 1.50 (1.37-1.62) | 1.63 (1.48-1.76) | 1.75 (1.58-1.89) | 1.86 (1.67-2.01) | 2.00 (1.78-2.17) | 2.11 (1.87-2.29) |
| 30-min | 1.19 (1.10-1.29) | 1.41 (1.30-1.53) | 1.69 (1.56-1.84) | 1.93 (1.77-2.09) | 2.22 (2.03-2.40) | 2.45 (2.23-2.65) | 2.67 (2.42-2.89) | 2.89 (2.60-3.13) | 3.18 (2.84-3.45) | 3.41 (3.02-3.71) |
| 60-min | 1.48 (1.37-1.61) | 1.77 (1.63-1.92) | 2.17 (2.00-2.36) | 2.52 (2.31-2.73) | 2.95 (2.70-3.20) | 3.32 (3.02-3.59) | 3.68 (3.33-3.98) | 4.06 (3.65-4.39) | 4.56 (4.07-4.94) | 4.98 (4.41-5.41) |
| 2-hr | 1.68 (1.54-1.83) | 2.01 (1.85-2.19) | 2.50 (2.30-2.72) | 2.94 (2.70-3.20) | 3.52 (3.21-3.81) | 4.00 (3.64-4.34) | 4.50 (4.07-4.88) | 5.03 (4.50-5.44) | 5.74 (5.09-6.21) | 6.34 (5.58-6.88) |
| 3-hr | 1.77 (1.62-1.95) | 2.12 (1.94-2.33) | 2.65 (2.42-2.91) | 3.14 (2.86-3.44) | 3.79 (3.43-4.15) | 4.36 (3.93-4.76) | 4.95 (4.43-5.40) | 5.59 (4.96-6.09) | 6.49 (5.68-7.08) | 7.27 (6.30-7.94) |
| 6-hr | 2.09 (1.91-2.32) | 2.51 (2.29-2.77) | 3.14 (2.86-3.46) | 3.72 (3.38-4.09) | 4.51 (4.08-4.95) | 5.21 (4.67-5.70) | 5.93 (5.29-6.48) | 6.72 (5.93-7.33) | 7.84 (6.83-8.55) | 8.81 (7.59-9.62) |
| 12-hr | 2.45 (2.23-2.72) | 2.93 (2.67-3.25) | 3.68 (3.35-4.07) | 4.39 (3.98-4.84) | 5.36 (4.83-5.89) | 6.22 (5.57-6.82) | 7.13 (6.32-7.81) | 8.13 (7.14-8.89) | 9.56 (8.27-10.4) | 10.8 (9.24-11.8) |
| 24-hr | 2.93 (2.73-3.18) | 3.54 (3.29-3.84) | 4.52 (4.19-4.90) | 5.39 (4.98-5.83) | 6.72 (6.16-7.28) | 7.89 (7.17-8.57) | 9.23 (8.27-10.0) | 10.7 (9.49-11.8) | 13.1 (11.3-14.4) | 15.1 (12.8-16.8) |
| 2-day | 3.42 (3.19-3.71) | 4.12 (3.84-4.46) | 5.23 (4.86-5.67) | 6.21 (5.75-6.74) | 7.72 (7.08-8.38) | 9.07 (8.22-9.86) | 10.6 (9.48-11.6) | 12.3 (10.9-13.6) | 15.0 (12.9-16.7) | 17.3 (14.6-19.5) |
| 3-day | 3.66 (3.41-3.95) | 4.39 (4.10-4.74) | 5.54 (5.15-5.97) | 6.54 (6.06-7.05) | 8.06 (7.40-8.70) | 9.39 (8.54-10.2) | 10.9 (9.79-11.9) | 12.6 (11.2-13.8) | 15.1 (13.2-16.8) | 17.4 (14.9-19.5) |
| 4-day | 3.89 (3.63-4.19) | 4.66 (4.36-5.02) | 5.84 (5.44-6.28) | 6.86 (6.37-7.37) | 8.39 (7.72-9.03) | 9.71 (8.87-10.5) | 11.2 (10.1-12.1) | 12.8 (11.4-14.0) | 15.3 (13.4-16.9) | 17.6 (15.1-19.6) |
| 7-day | 4.55 (4.27-4.88) | 5.44 (5.10-5.82) | 6.72 (6.28-7.18) | 7.79 (7.27-8.32) | 9.34 (8.65-9.99) | 10.6 (9.79-11.4) | 12.0 (11.0-13.0) | 13.5 (12.2-14.7) | 15.8 (14.0-17.3) | 18.0 (15.8-19.9) |
| 10-day | 5.27 (4.96-5.59) | 6.28 (5.92-6.68) | 7.65 (7.19-8.12) | 8.76 (8.22-9.31) | 10.3 (9.65-11.0) | 11.6 (10.8-12.4) | 13.0 (12.0-13.9) | 14.4 (13.2-15.5) | 16.5 (14.9-17.9) | 18.4 (16.4-20.1) |
| 20-day | 7.05 (6.68-7.45) | 8.34 (7.91-8.82) | 9.96 (9.43-10.5) | 11.3 (10.7-12.0) | 13.2 (12.4-13.9) | 14.7 (13.7-15.6) | 16.2 (15.1-17.3) | 17.9 (16.5-19.2) | 20.2 (18.4-21.8) | 22.0 (19.8-23.9) |
| 30-day | 8.69 (8.28-9.13) | 10.2 (9.76-10.8) | 12.0 (11.5-12.7) | 13.5 (12.8-14.2) | 15.3 (14.5-16.2) | 16.8 (15.8-17.8) | 18.3 (17.1-19.4) | 19.8 (18.4-21.0) | 21.7 (20.1-23.3) | 23.3 (21.3-25.1) |
| 45-day | 10.9 (10.4-11.4) | 12.8 (12.2-13.3) | 14.8 (14.1-15.5) | 16.4 (15.6-17.1) | 18.5 (17.8-19.4) | 20.2 (19.1-21.2) | 21.8 (20.5-22.9) | 23.4 (22.0-24.7) | 25.5 (23.7-27.1) | 27.1 (25.1-29.0) |
| 60-day | 13.0 (12.4-13.5) | 15.2 (14.5-15.9) | 17.4 (16.7-18.2) | 19.2 (18.3-20.1) | 21.5 (20.5-22.5) | 23.2 (22.1-24.3) | 24.9 (23.6-26.2) | 26.5 (25.0-28.0) | 28.6 (26.8-30.4) | 30.2 (28.1-32.2) |

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

Appendix C – Hydrologic Parameters Example for Subcatchments (All Subcatchments Data Provided in Zipped File)

Moses Drive Area – Subcatchment R64



Hydrologic Soil Group

| Map unit symbol | Map unit name | Rating | Acres in AOI | Percent of AOI |
|-----------------------------|--|--------|--------------|----------------|
| NcA | Noboco loamy sand, 0 to 2 percent slopes | C | 0.0 | 1.1% |
| RaA | Rains sandy loam, 0 to 2 percent slopes | B/D | 1.2 | 98.9% |
| Totals for Area of Interest | | | 1.2 | 100.0% |

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

| RUNOFF CURVE NUMBER & Tc | | | | | | | | |
|--|---|--|---|----------|---|------------|--------------|-------|
| Client: | SC Office of Resilience | | | SCS Eqn. | Lag (hrs) = $L^{0.8}((1000/CN-10)+1)^{0.7}/1900Y^{0.5}$ | | | |
| Proj Name: | Darlington Co. Watershed Study - Moses Dr | | | | Tc (min) = Lag * 1.67 * 60 | | | |
| Basin Name: | R64 | | | | | | | |
| COMMENTS: | Existing Conditions | | | | | | | |
| Cover Type Treatment | | Curve Numbers for Hydrologic Soil Type | | | | Basin Name | R64 | |
| | | hydrologic condition | A | B | C | D | Outlet Name | J46 |
| CULTIVATED AGRICULTURAL LANDS | | | | | | | | |
| Fallow | Bare soil | --- | 77 | 86 | 91 | 94 | DA, ac | 1.2 |
| | Crop residue (CR) | poor | 76 | 85 | 90 | 93 | Length, ft | 419 |
| | Crop residue (CR) | good | 74 | 83 | 88 | 90 | Slope, % | 0.191 |
| Row Crops | Straight row (SR) | poor | 72 | 81 | 88 | 91 | CN | 79 |
| | Straight row (SR) | good | 67 | 78 | 85 | 89 | Lag, hr | 0.37 |
| Other Agricultural Land | Pasture, grassland or range | fair | 49 | 69 | 79 | 84 | Tc, min | 37.5 |
| | Meadow -cont. grass (non grazed) | --- | 30 | 58 | 71 | 78 | Min. Tc, min | 37.5 |
| | Brush - brush, weed, grass mix | fair | 35 | 56 | 70 | 77 | us elev | 147.6 |
| | Woods - grass combination | fair | 43 | 65 | 76 | 82 | ds elev | 146.8 |
| | Woods | fair | 36 | 60 | 73 | 79 | S % | 0.191 |
| | Farmsteads | --- | 59 | 74 | 82 | 86 | | |
| FULLY DEVELOPED URBAN AREAS (Veg Established) | | | | | | | | |
| Open space (Lawns, parks etc.) | Fair condition; grass cover 50% to 75 % | | A | B | C | D | | |
| | | | 49 | 69 | 79 | 84 | | |
| Impervious Areas | Paved parking lots, roofs, driveways | | 98 | 98 | 98 | 98 | | |
| | Streets and roads | | | | | | | |
| | Paved; curbs and storm sewers | | 98 | 98 | 98 | 98 | | |
| | Paved; open ditches (w/right-of-way) | | 83 | 89 | 92 | 93 | | |
| | Gravel (w/ right-of-way) | | 76 | 85 | 89 | 91 | | |
| | Dirt (w/ right-of-way) | | 72 | 82 | 87 | 89 | | |
| Urban Districts | Avg % imperv | | | | | | | |
| | Commercial & business | 85 | 89 | 92 | 94 | 95 | | |
| | Industrial | 72 | 81 | 88 | 91 | 93 | | |
| Residential districts by average lot size | Avg % imperv | | | | | | | |
| | 1/8 acre (town houses) | 65 | 77 | 85 | 90 | 92 | | |
| | 1/4 acre | 38 | 61 | 75 | 83 | 87 | | |
| | 1/3 acre | 30 | 57 | 72 | 81 | 86 | | |
| | 1/2 acre | 25 | 54 | 70 | 80 | 85 | | |
| | 1 acre | 20 | 51 | 68 | 79 | 84 | | |
| | 2 acre | 12 | 46 | 65 | 77 | 82 | | |
| User defined urban | | ** | ** | ** | ** | ** | | |
| DEVELOPING URBAN AREA (No Vegetation) | | | | | | | | |
| | Newly graded area (pervious only) | | 77 | 86 | 91 | 94 | | |
| | | | 0 | 0 | 0 | 1.2 | | |
| | | | Total Acres | | 1.2 | | | |
| | | | Weighted Runoff Curve Number (RCN) | | 79 | | | |

Appendix D – PCSWMM Output (10-year Storm Event)

(All PCSWMM Models Data Provided in Zipped File)

a. – Moses PCSWMM Output

| Junction Name | Invert Elev. (ft) | Rim Elev. (ft) | Max. HGL (ft) |
|---------------|-------------------|----------------|---------------|
| J1 | 149.18 | 151.18 | 150.89 |
| J101 | 148.77 | 150.77 | 149.52 |
| J102 | 148.68 | 150.58 | 149.23 |
| J103 | 146.81 | 148.81 | 148.05 |
| J107 | 147.5 | 149.57 | 148.57 |
| J108 | 147.3 | 149.43 | 148.55 |
| J109 | 147.1 | 149.51 | 148.52 |
| J11 | 148.68 | 150.77 | 150.46 |
| J110 | 147 | 149.36 | 148.47 |
| J111 | 146.98 | 149.16 | 148.45 |
| J112 | 146.95 | 149.23 | 148.32 |
| J113 | 146.92 | 149.27 | 148.25 |
| J114 | 146.9 | 149.31 | 147.91 |
| J115 | 146.6 | 149.38 | 147.65 |
| J117 | 148.1 | 150.58 | 149.14 |
| J118 | 149.52 | 151.52 | 149.99 |
| J12 | 149.28 | 151.28 | 150.88 |
| J120 | 149.38 | 150.18 | 150.23 |
| J121 | 147.77 | 149.77 | 149 |
| J125 | 146.5 | 148.09 | 148.01 |
| J126 | 146.45 | 148.45 | 147.85 |
| J13 | 149.39 | 151.39 | 150.91 |
| J14 | 148.99 | 150.99 | 149.7 |
| J15 | 148.91 | 150.91 | 149.68 |
| J16 | 148.17 | 150.17 | 149.68 |
| J17 | 147.92 | 149.92 | 149.64 |
| J18 | 147.87 | 149.87 | 149.64 |
| J19 | 147.81 | 149.81 | 149.74 |
| J2 | 149.15 | 151.05 | 150.88 |
| J20 | 147.77 | 149.77 | 149.75 |
| J21 | 147.88 | 149.88 | 149.79 |
| J22 | 147.66 | 149.75 | 149.26 |

| | | | |
|-----|---------|--------|--------|
| J23 | 147.63 | 149.65 | 149.21 |
| J24 | 147.74 | 150 | 149.3 |
| J25 | 147.78 | 150 | 149.34 |
| J26 | 148.01 | 149.93 | 149.47 |
| J27 | 148.05 | 150.17 | 149.92 |
| J29 | 147.886 | 150.16 | 149.41 |
| J3 | 148.94 | 151.14 | 150.82 |
| J31 | 148.85 | 151.06 | 150.77 |
| J33 | 146.71 | 149.64 | 148.97 |
| J35 | 148.85 | 150.85 | 150.8 |
| J36 | 144.3 | 148.7 | 146.58 |
| J37 | 144.5 | 144.95 | 146.58 |
| J38 | 146.42 | 148.92 | 147.46 |
| J39 | 148.93 | 150.93 | 150.82 |
| J4 | 148.88 | 150.86 | 150.81 |
| J40 | 147.84 | 149.88 | 149.35 |
| J41 | 147.87 | 150.02 | 149.39 |
| J42 | 149.96 | 151.96 | 150.57 |
| J44 | 149.79 | 151.79 | 150.3 |
| J45 | 144.6 | 146 | 146.58 |
| J46 | 143.5 | 147 | 147.65 |
| J48 | 147.28 | 149.28 | 149.05 |
| J49 | 145.5 | 148.5 | 147.67 |
| J5 | 148.74 | 150.91 | 150.75 |
| J50 | 143.1 | 150 | 146.46 |
| J66 | 146 | 149.17 | 147.15 |
| J7 | 148.54 | 151.26 | 150.4 |
| J70 | 143.54 | 148.54 | 146.53 |
| J73 | 143.26 | 148.26 | 146.46 |
| J74 | 144.52 | 146.52 | 146.6 |
| J76 | 145 | 146.79 | 146.59 |
| J77 | 144.92 | 146.75 | 146.59 |
| J78 | 144.8 | 146.72 | 146.59 |
| J79 | 144.78 | 146.87 | 146.58 |
| J8 | 148.5 | 151.09 | 150.26 |
| J83 | 149.28 | 151.28 | 150.35 |
| J88 | 146.55 | 149.6 | 148.72 |
| J89 | 148.08 | 149.58 | 148.76 |
| J9 | 148.29 | 150.76 | 150.17 |
| J90 | 145.83 | 148.33 | 147.63 |
| J91 | 144 | 147.9 | 147.65 |

| | | | |
|-----|--------|--------|--------|
| J92 | 147.22 | 150.22 | 148.36 |
| J93 | 147.99 | 149.99 | 148.43 |
| J94 | 148.16 | 150.16 | 148.7 |
| J95 | 148.69 | 150.69 | 149.3 |
| J96 | 148.84 | 150.84 | 149.13 |
| J97 | 147.74 | 149.74 | 149.06 |
| J98 | 146.61 | 149.5 | 148.92 |

| Conduit Name | Length (ft) | Cross-Section | Diameter/Bottom Width, ft | No. of Pipes | Slope (ft/ft) | Max. Flow (cfs) | Max. Velocity (ft/s) |
|--------------|-------------|---------------|---------------------------|--------------|---------------|-----------------|----------------------|
| C1 | 56.799 | CIRCULAR | 1.25 | 1 | 0.05201 | 1.32 | 2.34 |
| C1.1 | 41.713 | TRAPEZOIDAL | 1.5 | 1 | 0.0012 | 7.9 | 1.36 |
| C10 | 45.407 | CIRCULAR | 1.5 | 1 | -0.00211 | 8.44 | 4.82 |
| C101 | 25.363 | CIRCULAR | 1.25 | 1 | 0.00789 | 3.05 | 2.78 |
| C103 | 25.259 | CIRCULAR | 1.25 | 1 | 0.00396 | 2.88 | 2.35 |
| C105 | 24.946 | CIRCULAR | 1.25 | 1 | 0.0012 | 4.66 | 3.8 |
| C107 | 25.032 | CIRCULAR | 1.25 | 1 | 0.0008 | 4.65 | 3.98 |
| C109 | 25.792 | CIRCULAR | 1.25 | 1 | 0.00969 | 3.18 | 3.43 |
| C11 | 26.412 | CIRCULAR | 1.5 | 1 | 0.00151 | 4.55 | 2.6 |
| C12 | 5.71 | CIRCULAR | 1.5 | 1 | 0 | 7.84 | 4.44 |
| C13 | 25.889 | CIRCULAR | 1.5 | 1 | 0.00116 | 5.47 | 3.11 |
| C14 | 70.436 | IRREGULAR | 0 | | 0.00142 | 13.32 | 0.94 |
| C15 | 26.009 | CIRCULAR | 1.25 | 1 | 0.00308 | 1.65 | 3.39 |
| C17 | 26.119 | CIRCULAR | 1.25 | 1 | 0.00957 | 2.83 | 2.31 |
| C19 | 25.938 | CIRCULAR | 1.25 | 1 | 0.00424 | 2.84 | 2.31 |
| C2 | 50.149 | CIRCULAR | 1.5 | 1 | 0.0012 | 8.08 | 4.57 |
| C21 | 26.109 | CIRCULAR | 1.25 | 1 | -0.0023 | 4.55 | 3.71 |
| C24 | 25.443 | CIRCULAR | 1.5 | 1 | 0.00118 | 2.56 | 1.46 |
| C26 | 41.679 | CIRCULAR | 1.5 | 2 | 0.0012 | 7.39 | 2.09 |
| C27 | 21.67 | CIRCULAR | 1.25 | 1 | 0.00508 | 3.23 | 2.7 |
| C3 | 25.927 | CIRCULAR | 1.5 | 1 | 0.00154 | 7.95 | 4.5 |
| C31 | 33.868 | CIRCULAR | 1.5 | 1 | 0.0124 | 5.17 | 5.72 |
| C33 | 42.783 | CIRCULAR | 1.5 | 1 | 0.00117 | 10.59 | 5.99 |
| C4 | 25.128 | CIRCULAR | 1.5 | 1 | 0.00119 | 4.7 | 2.72 |
| C44 | 36.48 | CIRCULAR | 1.5 | 1 | 0.01426 | 5.53 | 3.78 |
| C5 | 44.159 | CIRCULAR | 1.5 | 1 | 0.00906 | 4.15 | 3.06 |
| C69 | 53.317 | CIRCULAR | 3 | 2 | 0.03434 | 40.06 | 5.07 |
| C7 | 26.267 | CIRCULAR | 1.5 | 1 | 0.00152 | 7.89 | 4.46 |
| C70 | 26.195 | CIRCULAR | 1.5 | 1 | 0.00267 | 6.44 | 3.81 |
| C72 | 25.792 | CIRCULAR | 1.5 | 1 | 0.0031 | 4.23 | 2.9 |
| C74 | 25.671 | CIRCULAR | 1.5 | 1 | 0.00078 | 4.52 | 2.61 |
| C78 | 35.802 | CIRCULAR | 1.25 | 1 | 0.03242 | 3.36 | 4.19 |
| C8 | 24.132 | CIRCULAR | 1.5 | 1 | 0.00414 | 4.72 | 2.67 |
| C81 | 27.096 | CIRCULAR | 1.25 | 1 | -0.00554 | 0.97 | 2.46 |
| C85 | 24.538 | CIRCULAR | 1.5 | 1 | 0.00693 | 1.57 | 3.24 |

| | | | | | | | |
|--------|--------|-------------|------|---|----------|-------|------|
| C87 | 31.683 | CIRCULAR | 1.5 | 1 | -0.00189 | 1.67 | 2.63 |
| C9 | 25.68 | CIRCULAR | 1.5 | 1 | 0.00156 | 9.06 | 5.19 |
| C90.1 | 26.087 | CIRCULAR | 1 | 1 | 0.07573 | 1.27 | 4.06 |
| C91 | 50.967 | CIRCULAR | 3 | 1 | 0.00118 | 24.48 | 4.33 |
| C94 | 33.553 | CIRCULAR | 1.5 | 1 | 0.00566 | 3.55 | 2.74 |
| C96 | 26.306 | CIRCULAR | 1.25 | 1 | 0.00342 | 1.81 | 3.38 |
| C97 | 25.75 | CIRCULAR | 1.5 | 1 | 0.00194 | 6.81 | 3.9 |
| Ch1 | 6.534 | TRAPEZOIDAL | 2 | | 0.00153 | 7.93 | 1.14 |
| Ch100 | 129.46 | TRAPEZOIDAL | 2 | | 0.00286 | 3.77 | 0.73 |
| Ch102 | 60.519 | TRAPEZOIDAL | 2 | | 0.0033 | 2.95 | 0.71 |
| Ch104 | 51.671 | TRAPEZOIDAL | 2 | | 0.00039 | 2.87 | 0.49 |
| Ch106 | 62.556 | TRAPEZOIDAL | 2 | | 0.00048 | 4.65 | 0.9 |
| Ch108 | 83.693 | TRAPEZOIDAL | 2 | | 0.00358 | 4.65 | 1.47 |
| Ch111 | 93.496 | TRAPEZOIDAL | 2 | | 0.00374 | 3.08 | 1.04 |
| Ch112 | 361.93 | TRAPEZOIDAL | 2 | | 0.00445 | 3.58 | 1.27 |
| Ch113 | 134.96 | TRAPEZOIDAL | 2 | | 0.0086 | 5.42 | 0.88 |
| Ch114 | 367.07 | TRAPEZOIDAL | 2 | | 0.00346 | 1.07 | 0.82 |
| Ch115 | 134.67 | TRAPEZOIDAL | 2 | | 0.00126 | 0.69 | 0.5 |
| Ch119 | 178.34 | TRAPEZOIDAL | 2 | | 0.00348 | 6.79 | 1.01 |
| Ch12 | 67.436 | TRAPEZOIDAL | 2 | | 0.00119 | 4.46 | 0.79 |
| Ch14 | 80.077 | TRAPEZOIDAL | 2 | | 0.00137 | 7.78 | 0.96 |
| Ch15 | 23.012 | TRAPEZOIDAL | 2 | | 0.0013 | 7.86 | 1.03 |
| Ch16 | 144.12 | TRAPEZOIDAL | 2 | | 0.00513 | 1.39 | 0.62 |
| Ch18 | 28.937 | TRAPEZOIDAL | 2 | | 0.00449 | 2.79 | 0.42 |
| Ch20 | 80.128 | TRAPEZOIDAL | 2 | | -0.0005 | 2.78 | 0.3 |
| Ch22 | 32.729 | TRAPEZOIDAL | 2 | | 0.00244 | 4.48 | 0.64 |
| Ch23 | 51.495 | TRAPEZOIDAL | 2 | | 0.00241 | 9.09 | 1.82 |
| Ch25 | 126.08 | TRAPEZOIDAL | 2 | | 0.00127 | 2.49 | 0.4 |
| Ch26 | 264.87 | TRAPEZOIDAL | 2 | | 0.00109 | 2.67 | 0.57 |
| Ch29 | 120.85 | TRAPEZOIDAL | 2 | | 0.00132 | 5.3 | 0.89 |
| Ch30 | 508.42 | TRAPEZOIDAL | 3 | | 0.00124 | 7.97 | 1.16 |
| Ch32 | 98.677 | TRAPEZOIDAL | 3 | | 0.00132 | 9.88 | 1.04 |
| Ch34 | 650.75 | IRREGULAR | 0 | | 0.00522 | 13.61 | 1.22 |
| Ch4 | 115.61 | TRAPEZOIDAL | 2 | | 0.00121 | 8.01 | 1.16 |
| Ch46 | 242.48 | TRAPEZOIDAL | 2 | | 0.0025 | 11.49 | 1.76 |
| Ch46.1 | 275.81 | TRAPEZOIDAL | 2 | | 0.00154 | 10.98 | 1.08 |
| Ch5.1 | 62.461 | TRAPEZOIDAL | 2 | | 0.00026 | 4.79 | 0.92 |
| Ch5.2 | 49.994 | TRAPEZOIDAL | 2 | | 0.0012 | 4.62 | 0.86 |
| Ch6 | 172.97 | TRAPEZOIDAL | 2 | | 0.00121 | 7.9 | 1.11 |
| Ch62 | 566.03 | IRREGULAR | 0 | | 0.00049 | 6.51 | 0.67 |
| Ch71 | 176.38 | TRAPEZOIDAL | 3 | | 0.00232 | 6.76 | 1.24 |
| Ch73 | 55.792 | TRAPEZOIDAL | 3 | | 0.00323 | 4.62 | 0.62 |
| Ch74 | 61.706 | TRAPEZOIDAL | 3 | | 0.02756 | 7.8 | 1.49 |
| Ch74.1 | 20.863 | TRAPEZOIDAL | 3 | | 0.00959 | 4.76 | 0.48 |
| Ch75 | 283.13 | IRREGULAR | 0 | | 0.00268 | 5.81 | 0.45 |
| Ch78 | 102.6 | TRAPEZOIDAL | 3 | | 0.00117 | 4.37 | 0.72 |
| Ch8 | 166.1 | TRAPEZOIDAL | 2 | | 0.0012 | 9.08 | 1.19 |
| Ch82 | 147.79 | TRAPEZOIDAL | 2 | | 0.00744 | 0.95 | 0.47 |

| | | | | | | | |
|----------|--------|-------------|------|---|---------|-------|------|
| Ch83 | 142.97 | TRAPEZOIDAL | 2 | | 0.00406 | 1.81 | 0.76 |
| Ch84 | 164.8 | TRAPEZOIDAL | 2 | | 0.00467 | 1.57 | 0.68 |
| Ch86 | 110.38 | TRAPEZOIDAL | 2 | | 0.01459 | 1.58 | 0.33 |
| Ch88 | 272.92 | TRAPEZOIDAL | 3 | | 0.00165 | 24.67 | 2.3 |
| Ch89 | 168.43 | TRAPEZOIDAL | 3 | | 0.0016 | 27.48 | 2.13 |
| Ch90 | 211.85 | TRAPEZOIDAL | 2 | | 0.01048 | 4.34 | 1.34 |
| Ch90.2 | 95.646 | TRAPEZOIDAL | 2 | | 0.01443 | 1.14 | 0.28 |
| Ch92 | 195.92 | TRAPEZOIDAL | 3 | | 0.00265 | 5.37 | 0.78 |
| Ch93 | 129.09 | TRAPEZOIDAL | 3 | | 0.00852 | 10.63 | 3.34 |
| Ch93.1 | 41.41 | TRAPEZOIDAL | 3 | | 0.03625 | 34.34 | 2.89 |
| Ch95 | 129.69 | TRAPEZOIDAL | 1.66 | | 0.00239 | 3.55 | 0.69 |
| Ch99 | 407.14 | TRAPEZOIDAL | 2 | | 0.00251 | 6.76 | 1.36 |
| ChDetOF1 | 514.34 | IRREGULAR | 0 | | 0.00097 | 33 | 0.52 |
| ChO37Det | 559.28 | IRREGULAR | 0 | | 0.00029 | 24.96 | 0.61 |
| ChOF1 | 307.94 | CIRCULAR | 3 | 1 | 0.00162 | 18.11 | 2.56 |

| Storage Junction | Invert Elev. (ft) | Rim Elev. (ft) | Storage Name | Max. Volume (1000 ft ³) |
|------------------|-------------------|----------------|--------------|-------------------------------------|
| J10 | 148.25 | 151.29 | BioRetention | 0.741 |
| J100 | 147 | 149 | BioRetention | 0.393 |
| J106 | 146.2 | 148.98 | BioRetention | 0.58 |
| J116 | 147.85 | 150.58 | BioRetention | 0.313 |
| J119 | 148.25 | 148.75 | BioRetention | 0.166 |
| J28 | 147.79 | 149.79 | BioRetention | 0.78 |
| J30 | 147.47 | 151.14 | BioRetention | 0.702 |
| J32 | 146.84 | 151.58 | BioRetention | 0.963 |
| J34 | 146.66 | 149.16 | BioRetention | 0.803 |
| J43 | 147.99 | 149.99 | BioRetention | 0.334 |
| J6 | 148.99 | 151.03 | BioRetention | 1.884 |
| J75 | 144.59 | 146.59 | BioRetention | 0.867 |
| J87 | 146.1 | 148.1 | BioRetention | 0.799 |

b. – Chestnut Street PCSWMM Output

| Junction Name | Rim Elev. (ft) | Max. HGL (ft) | Invert Elev. (ft) |
|---------------|----------------|---------------|-------------------|
| J1 | 150.47 | 149.37 | 147.711 |
| J10 | 151.1 | 148.57 | 146.926 |
| J11 | 151.45 | 148.59 | 147.86 |
| J12 | 151.33 | 148.59 | 147.733 |
| J13 | 150.5 | 148.51 | 146.28 |
| J14 | 150.31 | 149.29 | 148.012 |
| J15 | 150.3 | 149.42 | 148.09 |
| J16 | 150.3 | 149.41 | 148.06 |
| J17 | 151.55 | 149.35 | 147.563 |
| J18 | 152.56 | 149.33 | 147.398 |
| J19 | 151.62 | 150.29 | 149.78 |
| J2 | 150.47 | 149.38 | 147.802 |
| J20 | 150.85 | 149.56 | 148.35 |
| J21 | 151.71 | 149.2 | 147.19 |
| J22 | 152.04 | 149.08 | 147.07 |
| J23 | 151.47 | 148.59 | 146.86 |
| J24 | 152.3 | 150.07 | 149.52 |
| J25 | 150.08 | 148.27 | 146.388 |
| J26 | 150.51 | 149.21 | 148.94 |
| J27 | 150.71 | 148.29 | 146.432 |
| J28 | 151.06 | 148.3 | 146.56 |
| J29 | 149.94 | 148.19 | 146.183 |
| J3 | 150.38 | 149.32 | 148.41 |
| J30 | 150.44 | 148.08 | 145.915 |
| J31 | 150.14 | 148.14 | 145.992 |
| J32 | 150 | 148.18 | 146 |
| J33 | 150 | 147.53 | 145.492 |
| J34 | 150.16 | 147.51 | 145.404 |
| J35 | 149.73 | 147.51 | 145.79 |
| J36 | 148 | 146.71 | 144.51 |
| J37 | 150 | 147.78 | 145.639 |
| J38 | 148 | 146.3 | 144.022 |
| J4 | 150.5 | 149.32 | 148.44 |
| J41 | 150.43 | 148.14 | 145.731 |
| J42 | 150.92 | 148.38 | 145.9 |
| J43 | 150.75 | 148.84 | 148.104 |

| | | | |
|-----|--------|--------|---------|
| J44 | 151.21 | 148.84 | 148.252 |
| J45 | 150.97 | 148.52 | 147.234 |
| J46 | 150.71 | 148.48 | 146.8 |
| J48 | 150.19 | 148.6 | 147.59 |
| J5 | 150.41 | 149.3 | 148.061 |
| J50 | 150.5 | 148.67 | 147.922 |
| J51 | 151 | 148.66 | 147.8 |
| J52 | 151 | 148.65 | 147.5 |
| J53 | 152 | 149.29 | 147.252 |
| J54 | 152 | 148.64 | 147.45 |
| J55 | 152 | 148.55 | 147.2 |
| J56 | 152 | 148.62 | 147.358 |
| J57 | 152 | 148.41 | 147.15 |
| J58 | 152 | 148.35 | 146.91 |
| J59 | 149 | 146.66 | 144.05 |
| J6 | 150.34 | 149.27 | 147.983 |
| J60 | 150.5 | 148.49 | 147 |
| J61 | 150.71 | 148.48 | 147.03 |
| J62 | 150 | 147.58 | 145.5 |
| J63 | 150.5 | 149.48 | 148.2 |
| J65 | 150.5 | 148.21 | 146.513 |
| J7 | 150.03 | 148.49 | 146.044 |
| J8 | 151.24 | 149.36 | 148 |
| J9 | 151.1 | 148.86 | 147.5 |

| Conduit Name | Length (ft) | Cross-Section | Diameter/Bottom Width, ft | No. of Pipes | Slope (ft/ft) | Max. Flow (cfs) | Max. Velocity (ft/s) |
|--------------|-------------|---------------|---------------------------|--------------|---------------|-----------------|----------------------|
| C1 | 121.297 | CIRCULAR | 1.5 | 1 | 0.00288 | 2.23 | 1.95 |
| C10 | 17.755 | CIRCULAR | 1.5 | 1 | 0.03799 | 4.81 | 3.34 |
| C11 | 337.513 | CIRCULAR | 2.25 | 1 | 0.00044 | 4.54 | 2.13 |
| C12 | 30.227 | CIRCULAR | 2 | 1 | 0.00126 | 7.36 | 3.5 |
| C13 | 67.312 | CIRCULAR | 1.25 | 1 | 0.03541 | 4.3 | 4.65 |
| C14 | 20.454 | CIRCULAR | 2 | 1 | 0.00137 | 7.36 | 3.83 |
| C15 | 148.489 | CIRCULAR | 1.5 | 1 | 0.00101 | 0.83 | 0.95 |
| C16 | 29.172 | CIRCULAR | 2 | 1 | 0.00103 | 3.16 | 1.74 |
| C17 | 143.022 | CIRCULAR | 2 | 1 | 0.00099 | 3.11 | 1.52 |
| C18 | 116.514 | CIRCULAR | 2.5 | 1 | 0.00103 | 12.83 | 3.04 |
| C19 | 196.32 | CIRCULAR | 2.5 | 1 | 0.00107 | 17.22 | 4.4 |
| C2 | 24.252 | CIRCULAR | 1.5 | 1 | 0.00082 | 2.68 | 1.72 |
| C20 | 291.636 | CIRCULAR | 2.5 | 2 | 0.00103 | 24.39 | 3.6 |
| C21 | 11.951 | CIRCULAR | 1 | 1 | 0.14285 | 8.22 | 19.73 |

| | | | | | | | |
|-----|---------|-------------|------|---|----------|-------|-------|
| C22 | 52.78 | CIRCULAR | 2.5 | 2 | 0.00083 | 35.05 | 5.6 |
| C23 | 79.711 | CIRCULAR | 2.5 | 2 | 0.00257 | 38.01 | 7.64 |
| C24 | 65.422 | CIRCULAR | 2.5 | 2 | 0.00292 | 27.91 | 3.28 |
| C25 | 38.945 | CIRCULAR | 2.5 | 2 | 0.00195 | 31.86 | 3.57 |
| C26 | 201.418 | CIRCULAR | 2.5 | 2 | 0.0013 | 32.67 | 3.68 |
| C27 | 132.832 | CIRCULAR | 2.5 | 2 | 0.00111 | 34.74 | 3.98 |
| C28 | 31.738 | CIRCULAR | 2.5 | 2 | 0.0023 | 37.02 | 4.28 |
| C29 | 497.742 | TRAPEZOIDAL | 3 | | 0.0016 | 46.65 | 2.41 |
| C3 | 23.607 | CIRCULAR | 1.25 | 1 | 0.01 | 1.97 | 1.6 |
| C30 | 104.35 | CIRCULAR | 2.5 | 1 | 0.00542 | 4.96 | 2.02 |
| C31 | 32.534 | CIRCULAR | 2 | 1 | 0.07032 | 0.85 | 2.88 |
| C32 | 38.443 | CIRCULAR | 1 | 1 | 0.00939 | 7.61 | 9.69 |
| C33 | 397.276 | TRAPEZOIDAL | 3 | | 0.00116 | 42.53 | 2.02 |
| C34 | 16.57 | CIRCULAR | 2 | 1 | 0.07273 | 5.47 | 2.97 |
| C35 | 20.139 | CIRCULAR | 2 | 1 | -0.18602 | 31.78 | 12.26 |
| C36 | 100.28 | CIRCULAR | 1 | 1 | 0.0001 | 1.02 | 2.25 |
| C37 | 231.424 | CIRCULAR | 3 | 1 | 0.00073 | 21.24 | 3.46 |
| C38 | 129.169 | CIRCULAR | 3 | 1 | 0.00081 | 18.91 | 3.09 |
| C39 | 169.631 | CIRCULAR | 3 | 1 | 0.00136 | 32.5 | 5.82 |
| C4 | 24.735 | CIRCULAR | 1.5 | 1 | 0.00117 | 2.68 | 1.68 |
| C40 | 334.022 | CIRCULAR | 2 | 1 | 0.00093 | 6.67 | 2.51 |
| C41 | 63.121 | CIRCULAR | 2.5 | 1 | 0.00217 | 11.96 | 2.92 |
| C42 | 97.013 | CIRCULAR | 2.5 | 1 | 0.00064 | 11.99 | 2.88 |
| C43 | 39.885 | CIRCULAR | 2.5 | 2 | 0.00321 | 28.96 | 4.54 |
| C44 | 26.486 | CIRCULAR | 1.5 | 1 | 0.004 | 1.04 | 1.45 |
| C45 | 175.389 | CIRCULAR | 1.5 | 1 | 0.00261 | 2.85 | 3.82 |
| C46 | 396.853 | CIRCULAR | 2.5 | 1 | 0.00116 | 6.67 | 1.49 |
| C47 | 27.022 | CIRCULAR | 2 | 1 | 0.00063 | 4.54 | 2.27 |
| C48 | 386.828 | TRAPEZOIDAL | 3 | | 0.00101 | 46.16 | 3.01 |
| C49 | 434.008 | CIRCULAR | 3 | 1 | 0.00157 | 23.58 | 4.22 |
| C5 | 248.891 | CIRCULAR | 1.5 | 1 | 0.00182 | 6.78 | 4.67 |
| C50 | 185 | CIRCULAR | 1.5 | 1 | 0.00204 | 0.54 | 1.31 |
| C51 | 163.799 | CIRCULAR | 1.5 | 1 | 0.00074 | 0.57 | 1.13 |
| C52 | 116.483 | CIRCULAR | 1.5 | 1 | 0.0016 | 0.7 | 1.09 |
| C53 | 117.381 | CIRCULAR | 1.5 | 1 | 0.0013 | 1.27 | 1.06 |
| C54 | 36.316 | CIRCULAR | 1.5 | 1 | 0.00132 | 2.32 | 1.56 |
| C55 | 139.21 | CIRCULAR | 1.5 | 1 | 0.0004 | 2.31 | 1.54 |
| C56 | 77.856 | CIRCULAR | 1.5 | 1 | 0.00064 | 4.17 | 2.98 |
| C57 | 29.25 | CIRCULAR | 1.5 | 1 | 0.0012 | 4.79 | 3.95 |
| C58 | 224.415 | CIRCULAR | 2 | 1 | 0.00086 | 5.58 | 2.54 |
| C59 | 578.389 | CIRCULAR | 2.5 | 1 | 0.00069 | 20.49 | 6.66 |
| C6 | 21.257 | CIRCULAR | 1.5 | 1 | 0.00141 | 1.07 | 1.59 |
| C60 | 34.076 | CIRCULAR | 1 | 1 | 0.00675 | 0.01 | 0.03 |
| C61 | 38.167 | CIRCULAR | 2 | 1 | 0.00524 | 4.11 | 1.88 |
| C62 | 120.661 | CIRCULAR | 2 | 1 | 0.00194 | 4.24 | 2.4 |
| C63 | 93.638 | CIRCULAR | 3 | 1 | 0.00214 | 38.92 | 15.61 |
| C64 | 88.014 | CIRCULAR | 2 | 1 | 0.00069 | 6.68 | 2.81 |
| C65 | 102.834 | CIRCULAR | 1.5 | 1 | 0.00107 | 0.83 | 1.02 |

| | | | | | | | |
|----|--------|----------|------|---|---------|------|------|
| C7 | 78.979 | CIRCULAR | 1.25 | 1 | 0.00022 | 2.23 | 1.81 |
| C8 | 26.741 | CIRCULAR | 1.5 | 1 | 0.00475 | 1.3 | 2.57 |
| C9 | 45.222 | CIRCULAR | 1.5 | 1 | 0.00148 | 1.4 | 2.81 |

| Storage Junction | Invert Elev. (ft) | Rim Elev. (ft) | Storage Name | Max. Volume (1000 ft ³) |
|------------------|-------------------|----------------|---------------|-------------------------------------|
| J39 | 143.65 | 149.34 | OF2Stor | 175.678 |
| J40 | 145.3 | 150.89 | ChestnutStor3 | 102.297 |
| J47 | 148.3 | 151 | ChestnutStor1 | 2.63 |
| J49 | 142.5 | 148.5 | ParkStor | 56.929 |

c. – M. L. King Drive PCSWMM Output

| Junction Name | Rim Elev. (ft) | Max. HGL (ft) | Invert Elev. (ft) |
|---------------|----------------|---------------|-------------------|
| J1 | 216.189 | 218.189 | 217.99 |
| J10 | 218.622 | 220.922 | 219.1 |
| J11 | 218.43 | 220.73 | 218.99 |
| J12 | 218.32 | 220.32 | 218.84 |
| J13 | 218.013 | 220.313 | 218.7 |
| J14 | 217.914 | 220.325 | 218.61 |
| J15 | 217.839 | 220.325 | 218.57 |
| J16 | 217.79 | 220.313 | 218.53 |
| J17 | 219.79 | 222.09 | 220.02 |
| J18 | 219.81 | 222.11 | 220.02 |
| J19 | 219.276 | 221.45 | 219.68 |
| J2 | 216.398 | 219.28 | 218 |
| J20 | 219.01 | 221.31 | 219.7 |
| J21 | 219.03 | 221.33 | 219.69 |
| J22 | 219.051 | 221.351 | 219.62 |
| J23 | 218.84 | 221.14 | 219.59 |
| J24 | 218.859 | 221.159 | 219.56 |
| J25 | 218.59 | 220.89 | 219.55 |
| J26 | 218.615 | 220.915 | 219.4 |
| J27 | 218.41 | 220.71 | 219.26 |
| J28 | 218.422 | 220.758 | 219.24 |
| J29 | 218.195 | 220.59 | 219.05 |
| J3 | 219.93 | 222.23 | 220.03 |
| J30 | 218.128 | 220.51 | 218.88 |
| J31 | 218.019 | 220.444 | 218.73 |
| J32 | 217.876 | 220.34 | 218.67 |
| J33 | 217.495 | 219.795 | 218.5 |
| J34 | 217.433 | 219.733 | 218.48 |
| J35 | 217.323 | 219.623 | 218.26 |
| J36 | 217.421 | 220.182 | 218.27 |
| J37 | 217.229 | 220.05 | 218.24 |
| J38 | 217.146 | 219.92 | 218.09 |
| J39 | 217.119 | 219.903 | 218.05 |
| J4 | 219.696 | 221.78 | 220.03 |
| J40 | 216.734 | 219.73 | 218.02 |
| J41 | 216.637 | 219.746 | 218.02 |

| | | | |
|-----|---------|---------|--------|
| J42 | 215.524 | 218 | 216.8 |
| J43 | 215.588 | 218.337 | 216.81 |
| J44 | 215.406 | 218 | 216.77 |
| J47 | 217.666 | 220.3 | 218.5 |
| J48 | 217.248 | 219.548 | 218.24 |
| J49 | 217.145 | 219.445 | 218.04 |
| J5 | 219.3 | 221.6 | 219.71 |
| J50 | 217.076 | 219.376 | 218.02 |
| J51 | 218.996 | 221.296 | 219.49 |
| J52 | 217.688 | 219.988 | 218.68 |
| J53 | 218.73 | 221.03 | 218.73 |
| J54 | 218.59 | 220.89 | 218.59 |
| J55 | 218.44 | 220.74 | 219.33 |
| J56 | 219 | 221.3 | 219 |
| J57 | 216.527 | 219.27 | 218.01 |
| J58 | 216.5 | 219.327 | 218.01 |
| J59 | 219.523 | 221.786 | 219.89 |
| J6 | 219.18 | 221.48 | 219.54 |
| J60 | 219.499 | 221.799 | 219.8 |
| J7 | 218.76 | 221.06 | 219.31 |
| J8 | 218.73 | 221.03 | 219.21 |
| J9 | 218.65 | 220.95 | 219.16 |

| Conduit Name | Length (ft) | Cross-Section | Diameter/Bottom Width, ft | No. of Pipes | Slope (ft/ft) | Max. Flow (cfs) | Max. Velocity (ft/s) |
|--------------|-------------|---------------|---------------------------|--------------|---------------|-----------------|----------------------|
| C1 | 38.978 | CIRCULAR | 1.25 | 1 | 0.00051 | 0 | 0.08 |
| C10 | 23.974 | TRAPEZOIDAL | 2 | | -0.0005 | 2.63 | 0.89 |
| C11 | 152.454 | TRAPEZOIDAL | 2 | | 0.00149 | 3.57 | 1.17 |
| C12 | 65.075 | TRAPEZOIDAL | 2 | | 0.00103 | 4.52 | 1.57 |
| C13 | 40.658 | TRAPEZOIDAL | 2 | | 0.00268 | 4.51 | 1.8 |
| C14 | 23.405 | TRAPEZOIDAL | 2 | | 0.00611 | 4.5 | 1.73 |
| C15 | 141.816 | TRAPEZOIDAL | 2.09 | | 0.00321 | 5.13 | 1.73 |
| C16 | 24.001 | TRAPEZOIDAL | 2 | | 0.008 | 6.26 | 1.77 |
| C17 | 71.504 | TRAPEZOIDAL | 2 | | 0.00116 | 6.23 | 1.69 |
| C18 | 20.008 | TRAPEZOIDAL | 2 | | 0.00135 | 6.18 | 1.9 |
| C19 | 66.692 | TRAPEZOIDAL | 2 | | 0.00577 | 6.12 | 1.52 |
| C2 | 224.283 | TRAPEZOIDAL | 2 | | 0.00238 | 0.37 | 0.57 |
| C20 | 19.71 | TRAPEZOIDAL | 2 | | 0.00492 | 6.03 | 1.13 |


| | | | | | | | |
|-----|----------|-------------|-------|---|---------|-------|------|
| C21 | 25.47 | TRAPEZOIDAL | 2 | | 0.00432 | 7.21 | 0.48 |
| C22 | 40.241 | TRAPEZOIDAL | 2 | | 0.00519 | 7.3 | 0.96 |
| C23 | 873.855 | TRAPEZOIDAL | 3 | | 0.00169 | 13.03 | 2.14 |
| C24 | 978.576 | TRAPEZOIDAL | 4 | | 0.00174 | 2.57 | 1.24 |
| C25 | 23.985 | CIRCULAR | 1.25 | 1 | 0.00976 | 0 | 0.08 |
| C26 | 77.295 | TRAPEZOIDAL | 2 | | 0.00224 | 0.84 | 0.88 |
| C27 | 24.896 | CIRCULAR | 1.25 | 1 | 0.00482 | 1.06 | 3.36 |
| C28 | 72.557 | TRAPEZOIDAL | 2 | | 0.00579 | 1.51 | 1.14 |
| C29 | 23.958 | CIRCULAR | 1.25 | 1 | 0.00125 | 1.51 | 3.15 |
| C3 | 23.498 | CIRCULAR | 1.25 | 1 | 0.01132 | 1.13 | 2.27 |
| C30 | 24.602 | CIRCULAR | 2 | 1 | 0.00325 | 1.51 | 2.53 |
| C31 | 23.899 | TRAPEZOIDAL | 2 | | 0.00117 | 1.8 | 1.23 |
| C32 | 57.067 | TRAPEZOIDAL | 2 | | 0.00336 | 1.8 | 1.17 |
| C33 | 28.957 | CIRCULAR | 1.25 | 1 | 0.0038 | 1.81 | 3.68 |
| C34 | 90.276 | TRAPEZOIDAL | 2 | | 0.0034 | 2.24 | 1.16 |
| C35 | 23.922 | CIRCULAR | 1.25 | 1 | 0.00414 | 2.42 | 3.55 |
| C36 | 44.301 | TRAPEZOIDAL | 2 | | 0.00169 | 2.41 | 1.04 |
| C37 | 15.183 | CIRCULAR | 1.25 | 1 | 0.00323 | 2.39 | 3.37 |
| C38 | 54.001 | TRAPEZOIDAL | 2 | | 0.0023 | 2.35 | 0.94 |
| C39 | 1021.499 | TRAPEZOIDAL | 2 | | 0.00197 | 3.53 | 1.19 |
| C4 | 109.952 | TRAPEZOIDAL | 2.211 | 1 | 0.00018 | 1.06 | 0.48 |
| C40 | 40.453 | CIRCULAR | 1.75 | 1 | 0.0022 | 2.86 | 1.58 |
| C41 | 34.403 | CIRCULAR | 1.75 | 1 | 0.00343 | 5.56 | 3.07 |
| C42 | 366.068 | TRAPEZOIDAL | 2 | | 0.00213 | 7.21 | 2.04 |
| C43 | 19.862 | CIRCULAR | 1.5 | 2 | 0.00312 | 5.78 | 2.24 |
| C44 | 129.261 | TRAPEZOIDAL | 2 | | 0.00085 | 5.78 | 1.46 |
| C45 | 20.158 | CIRCULAR | 1.5 | 2 | 0.00372 | 6.24 | 2.61 |
| C46 | 81.274 | TRAPEZOIDAL | 2 | | 0.00127 | 6.23 | 1.84 |
| C47 | 19.852 | CIRCULAR | 1.5 | 2 | 0.00348 | 6.19 | 3.26 |
| C48 | 118.521 | TRAPEZOIDAL | 2 | | 0.00748 | 6.35 | 1.29 |
| C49 | 451.196 | TRAPEZOIDAL | 2 | | 0.00196 | 1.59 | 1 |
| C5 | 23.496 | CIRCULAR | 1.25 | 1 | 0.00089 | 1.35 | 2.29 |
| C50 | 110.212 | TRAPEZOIDAL | 2 | | 0.00175 | 5.79 | 1.46 |
| C51 | 102.27 | TRAPEZOIDAL | 2 | | 0.00171 | 2.64 | 0.87 |
| C52 | 127.656 | TRAPEZOIDAL | 2 | | 0.00024 | 2.59 | 0.81 |
| C53 | 19.737 | TRAPEZOIDAL | 2 | | 0.00137 | 7.06 | 1.04 |
| C54 | 45.173 | TRAPEZOIDAL | 2.183 | | 0.00226 | 6.99 | 0.96 |
| C55 | 5.727 | CIRCULAR | 1.25 | 1 | 0.00419 | 0.87 | 3.29 |
| C56 | 58.596 | TRAPEZOIDAL | 2 | | 0.0034 | 0.83 | 0.87 |

| | | | | | | | |
|----|--------|-------------|------|---|---------|------|------|
| C6 | 74.561 | TRAPEZOIDAL | 2 | | 0.00283 | 1.48 | 0.73 |
| C7 | 23.79 | CIRCULAR | 1.25 | 1 | -0.0008 | 1.44 | 2 |
| C8 | 33.173 | CIRCULAR | 1.25 | 1 | 0.00075 | 1.48 | 1.65 |
| C9 | 62.826 | TRAPEZOIDAL | 2 | | 0.00428 | 1.55 | 0.54 |


| Storage Junction | Invert Elev. (ft) | Rim Elev. (ft) | Storage Name | Max. Volume (1000 ft ³) |
|------------------|-------------------|----------------|--------------|-------------------------------------|
| J45 | 214.075 | 217.28 | MLKStor2 | 90.862 |

Appendix E – 10% Concept Plans and Profiles

**DARLINGTON COUNTY H&H STUDY
PROPOSED CONDITIONS - MOSES DR.
FOR
SOUTH CAROLINA OFFICE OF RESILIENCE**



SITE MAP
SCALE: 1"=5,000'



LOCATION MAP

**SCOR PROJECT NUMBER PP-21-1600-01
ELR PROJECT NUMBER 1822005**

10% PLANS SUBMITTAL

MARCH 24, 2023

**PRELIMINARY
NOT FOR CONSTRUCTION**

The Palmetto Utility Protection Service, Inc.
810 Dutch Square Boulevard, Suite 220 Columbia, South Carolina 29210 Voice (803) 939-1117 Fax (803) 939-0704



3 DAYS BEFORE DICING IN SOUTH CAROLINA
CALL 1-888-721-7877

UNDERGROUND LOCATORS. CONTRACTOR SHALL CONTACT THE UNDERGROUND LOCATORS EVERY 10 DAYS FOR AN UPDATE TO UTILITY LOCATIONS.
Call BEFORE you DIG!


| DRAWING INDEX | |
|---------------|---------------------------------|
| CIVIL | |
| C0.0 | COVER SHEET |
| C1.1 | EXISTING CONDITIONS |
| C2.1 | STORM DRAINAGE PLAN |
| C2.2 | STORM DRAINAGE TABLES AND NOTES |
| C3.1-C3.5 | STORM DRAINAGE PROFILES |
| C4.1-C4.2 | DETAILS |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

SOUTH CAROLINA OFFICE OF RESILIENCE
ATTN: PHLEISHA LEWIS
632 ROSEWOOD DRIVE
COLUMBIA, SC 29201
PHLEISHA.LEWIS@SCOR.SC.GOV
Phone: (803) 543-0018




**E.L. ROBINSON
ENGINEERING**
1301 Gervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com

PROJECT COORDINATES
LATITUDE: 34° 21' 10" N
LONGITUDE: 80° 04' 39" W


| | | | |
|------------------|-------|---|-------------------------------|
| DRAWN: CWS | SEAL: | COA:  | SHEET NO. C0.0 |
| CHECKED: DKB | | | PROJECT NO. 1822005 |
| APPROVED: DKB | | | |



**PRELIMINARY
NOT FOR CONSTRUCTION**



**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com




**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|-------------|----------|
| Project No. | 1822015 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DRB |
| Drawn By | CWS |
| Approved By | DRB |


**EXISTING
CONDITIONS
PLAN**

Drawing No.
C1.1



**PRELIMINARY
NOT FOR CONSTRUCTION**

**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

Drawing Information

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | OWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PLAN**

Drawing No.
C2.1

CONDUIT TABLE

| |
|--|
| |
|--|

JUNCTION TABLE

| |
|--|
| |
|--|

SEQUENCE OF CONSTRUCTION

- ITEMS MUST OCCUR IN THE ORDER LISTED; ITEMS CANNOT OCCUR CONCURRENTLY UNTIL SPECIFICALLY NOTED.
1. RECEIVE NPDES COVERAGE FROM SCDHEC.
 2. PRE-CONSTRUCTION MEETING WITH DARLINGTON COUNTY STORMWATER MANAGEMENT STAFF PRESENT.
 3. THE PROJECT IS A LINEAR DITCH IMPROVEMENT, CLEANING AND REGRADING OF DITCHES, AND INSTALLATION OF STORM DRAINAGE AND BOXES. AS SUCH, THE CONTRACTOR SHALL SCHEDULE HIS WORK TO COMPLETE IN SECTIONS. IT IS NOT INTENDED FOR THE ENTIRE PROJECT TO BE DISTURBED AT ONE TIME.
 4. LIMIT WORK BETWEEN ROADS CROSSINGS COMPLETING EACH CLEANING AND REGRADING BETWEEN ROADS COMPLETELY INCLUDING STABILIZATION BEFORE PROCEEDING TO THE NEXT AREA.
 5. DISTURBANCE SHOULD BE GENERALLY LIMITED TO 1,000 LF MAX WITH EROSION CONTROL AS "ROLLING" WITH THE PROJECT.
 6. ALL EXISTING INLETS SHALL BE PROTECTED BY SEDIMENT TUBES AS DETAILED IN THESE PLANS.
 7. ALL NEW INLETS SHALL BE PROTECTED BY SEDIMENT TUBE PLACED IN A CIRCULAR FASHION AS DETAILED IN THESE PLANS.
 8. NOTIFY DARLINGTON COUNTY STORMWATER MANAGEMENT STAFF 48 HOURS PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES.
 9. INSTALLATION OF CONSTRUCTION ENTRANCES.
 10. CLEARING AND GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS.
 11. INSTALLATION OF PERIMETER CONTROLS (E.G. SILT FENCE).
 12. CLEARING AND GRUBBING OF SITE AND TREE REMOVAL. (SEDIMENT AND EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED).
 13. TOP SOIL REMOVAL AND STOCKPILE WITH SILT FENCE AROUND PERIMETER.
 14. CLEANING AND CLEARING OF CHANNELS INDICATED ON THE PLANS..
 15. INSTALLATION OF CHECK DAMS IN CHANNEL.
 16. REMOVAL OF TREES, DEBRIS, AND OTHER ITEMS FROM CHANNEL.
 17. REGRADING DITCHES IN THE AREAS SHOWN IN THE PLANS..
 18. EXCAVATION OF OVBANK PER GRADING PLAN.
 19. INSTALL NEW STORM PIPING AND BOXES.
 20. INSTALL ENKAMAT BANK STABILIZATION AND/OR FLEXTERRA AND/OR HYDROSEEDING.
 21. PERMANENT/FINAL STABILIZATION TO OTHER AREAS DISTURBED..
 22. REMOVAL OF TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED (THE DEPARTMENT RECOMMENDS THAT THE PROJECT OWNER/OPERATOR HAVE THE SWPPP PREPARER OR REGISTRATION EQUIVALENT APPROVE THE REMOVAL OF TEMPORARY STRUCTURES.)
 23. PREPARE A DETAILED AS-BUILT SURVEY OF THE STRUCTURES AND GRADED AREAS FOR SUBMITTAL TO THE CITY, SCDHEC, AND FEMA.

ONCE CONSTRUCTION IS COMPLETE THE ITEMS BELOW MUST BE PERFORMED IN THE ORDER SHOWN.

24. SUBMIT NOTICE OF TERMINATION (NOT) TO DARLINGTON COUNTY AND SCDHEC. MANAGEMENT STAFF.

• NOTE: MAINTENANCE OF SEDIMENT AND EROSION CONTROL MEASURES MUST CONTINUE UNTIL THE SITE IS PERMANENTLY STABILIZED AND THE CONTROLS ARE REMOVED.

CONTRACTOR NOTES

1. PRIOR TO BEGINNING CONSTRUCTION, THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED FROM ALL REGULATORY AUTHORITIES.
2. CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY TRENCHING OR EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. FOR ASSISTANCE WITH FIELD LOCATION OF EXISTING UTILITIES THE CONTRACTOR CAN CONTACT PUPS AT 1-888-721-7877.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL ILLUSTRATED KNOWN UNDERGROUND ELEMENTS. ADDITIONALLY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXERCISING REASONABLE EFFORT TO PROTECT ANY UNKNOWN UNDERGROUND ELEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF UNKNOWN ELEMENTS ARE DISCOVERED THAT WOULD NECESSITATE MODIFICATION TO THE ILLUSTRATED DESIGN.
5. THE CONTRACTOR SHALL PROTECT ALL ADJACENT PROPERTIES, THE GENERAL PUBLIC, AND ALL OTHER FACILITIES. SHOULD DAMAGES OCCUR, CONTRACTOR SHALL REPAIR IMMEDIATELY AS DIRECTED BY THE MANAGER/OWNER. CONTRACTOR IS FINANCIALLY RESPONSIBLE FOR ALL REPAIRS, AND REPAIRS ARE TO BE PERFORMED TO THE DEVELOPER'S APPROVAL.
6. THE CONTRACTOR SHALL UTILIZE SIGNS, BARRICADES, FLAGMEN, OR GUARDS AS REQUIRED TO ENSURE THE SAFETY OF ALL VEHICULAR AND PEDESTRIAN TRAFFIC DURING ALL CONSTRUCTION ACTIVITIES.
7. ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
8. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.
9. THE GENERAL CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND RIGHT-OF-WAYS, PUBLIC OR PRIVATE, PRIOR TO WORKING IN THESE AREAS.
10. CONTRACTOR TO BE RESPONSIBLE FOR SECURING THE SITE PRIOR TO SUBSTANTIAL COMPLETION OF THE PROJECT. REPAIRS, RESULTING FROM VANDALISM, TO BE AT HIS OWN EXPENSE.

EROSION CONTROL NOTES

1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO GRASSING/HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED. EXCEPT AS STATED BELOW.
 - » WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - » WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION, IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE IS STABILIZED.
6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ AND SCR100000.
8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
9. ALL WATERS OF THE STATE (WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10-FT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.
10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
11. A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT THE FINAL STABILIZATION IS REACHED.
12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF SEVEN (7) CALENDAR DAYS.
13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
 - » WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL
 - » WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FROM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS
 - » FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE
 - » SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING
17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
18. IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB MORE THAN 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.
20. SILT FENCING LINE ON EROSION CONTROL PLAN SHEETS ARE SHOWN FOR GRAPHICAL PURPOSES. SILT FENCING SHALL BE PLACED AT THE LIMITS OF DISTURBANCE

**PRELIMINARY
NOT FOR CONSTRUCTION**

PALMETTO UTILITY PROTECTION SERVICE




Don't Dig! Before you call
toll free 1-888-721-7877

A one call system for community and job safety.

**EL. ROBINSON
ENGINEERING**

1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com







**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revision No. | Name | Date |
|--------------|------|------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

**STORM DRAINAGE
TABLES AND NOTES**

C2.2




**PRELIMINARY
NOT FOR CONSTRUCTION**

LEGEND

- 2-YEAR FLOODPLAIN
- 10-YEAR FLOODPLAIN
- TOP OF PIPE/CHANNEL
- BOTTOM OF PIPE/CHANNEL

**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Revisions





| No. | Name | Date |
|-----|------|------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Drawing Information

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Date | 03.24.23 |
| Approved By | DKB |


**STORM
DRAINAGE
PROFILES**

Drawing No. **C3.1**



**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|--------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| ----- | 10-YEAR FLOODPLAIN |
| ————— | TOP OF PIPE/CHANNEL |
| ————— | BOTTOM OF PIPE/CHANNEL |



**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information





| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

| Drawing Information | |
|---------------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**

Drawing No.

C3.2




| LEGEND | |
|--------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| ----- | 10-YEAR FLOODPLAIN |
| ——— | TOP OF PIPE/CHANNEL |
| ——— | BOTTOM OF PIPE/CHANNEL |

**PRELIMINARY
NOT FOR CONSTRUCTION**



**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information


| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Drawing Information

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Date | 03.24.23 |
| Approved By | DKB |


**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.3



Junction #94
Rim Elev. = 150.16 ft
Invert Elev. = 148.16 ft


Junction #88
Rim Elev. = 149.64 ft
Invert Elev. = 146.55 ft



Junction #94
Rim Elev. = 150.16 ft
Invert Elev. = 148.16 ft

Junction #93
Rim Elev. = 149.99 ft
Invert Elev. = 147.99 ft

Junction #92
Rim Elev. = 150.22 ft
Invert Elev. = 147.22 ft



Junction #95
Rim Elev. = 150.69 ft
Invert Elev. = 148.69 ft


Junction #96
Rim Elev. = 150.84 ft
Invert Elev. = 148.84 ft

Junction #97
Rim Elev. = 148.74 ft
Invert Elev. = 147.74 ft

Junction #92
Rim Elev. = 150.22 ft
Invert Elev. = 147.22 ft

Storage #106
Rim Elev. = 148.88 ft
Invert Elev. = 146.2 ft

Junction #90
Rim Elev. = 148.83 ft
Invert Elev. = 145.83 ft



Junction #118
Rim Elev. = 151.52 ft
Invert Elev. = 149.52 ft

Storage #119
Rim Elev. = 150.25 ft
Invert Elev. = 148.25 ft

Junction #99
Rim Elev. = 150.08 ft
Invert Elev. = 148.08 ft


Junction #88
Rim Elev. = 149.64 ft
Invert Elev. = 146.55 ft

**PRELIMINARY
NOT FOR CONSTRUCTION**

LEGEND

- 2-YEAR FLOODPLAIN
- 10-YEAR FLOODPLAIN
- TOP OF PIPE/CHANNEL
- BOTTOM OF PIPE/CHANNEL

**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



Project Title / Client Information





**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|---------------------|---------------------|
| Drawing Information | Project No. 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**


Drawing No.
C3.4



**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|--------|------------------------|
| | 2-YEAR FLOODPLAIN |
| | 10-YEAR FLOODPLAIN |
| | TOP OF PIPE/CHANNEL |
| | BOTTOM OF PIPE/CHANNEL |

**EL. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS**





SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | |
|-----------|------|
| No. | Name |
| | |
| | |
| | |
| | |
| | |

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | CYS |
| Date | 03.24.23 |
| Checked By | DHB |
| Date | 04.24.23 |
| Approved By | DHB |

**STORM
DRAINAGE
PROFILES**

C3.5



PRELIMINARY
NOT FOR CONSTRUCTION

E.L. ROBINSON ENGINEERING
1301 Gervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com

CERTIFIED PROFESSIONAL ENGINEER
No. 2544


DARLINGTON COUNTY
H&H STUDY - MOSES DR.
PROPOSED CONDITIONS
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |


DETAILS

Drawing No. **C4.2**

DARLINGTON COUNTY H&H STUDY PROPOSED CONDITIONS - CHESTNUT ST. FOR SOUTH CAROLINA OFFICE OF RESILIENCE



SITE MAP
SCALE: 1"=5,000'



LOCATION MAP

SCOR PROJECT NUMBER PP-21-1600-01
ELR PROJECT NUMBER 1822005

10% PLANS SUBMITTAL

MARCH 24, 2023

**PRELIMINARY
NOT FOR CONSTRUCTION**

The Palmetto Utility Protection Service, Inc.
810 Dutch Square Boulevard, Suite 220 Columbia, South Carolina 29210 Voice (803) 939-1117 Fax (803) 939-0704



3 DAYS BEFORE DICING IN
SOUTH CAROLINA
CALL 1-888-721-7877

UNDERGROUND LOCATORS.
CONTRACTOR SHALL CONTACT
THE UNDERGROUND LOCATORS
EVERY 10 DAYS FOR AN UPDATE
TO UTILITY LOCATIONS.

Call BEFORE you DIG!

DRAWING INDEX

CIVIL

| | |
|-----------|---------------------------------|
| C0.0 | COVER SHEET |
| C1.1 | EXISTING CONDITIONS |
| C2.1 | STORM DRAINAGE PLAN |
| C2.2 | STORM DRAINAGE TABLES AND NOTES |
| C3.1-C3.5 | STORM DRAINAGE PROFILES |
| C4.1-C4.2 | DETAILS |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

SOUTH CAROLINA OFFICE OF RESILIENCE


ATTN: PHLEISHA LEWIS
632 ROSEWOOD DRIVE
COLUMBIA, SC 29201
PHLEISHA.LEWIS@SCOR.SC.GOV
Phone: (803) 543-0018



**E.L. ROBINSON
ENGINEERING**
1301 Gervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com


PROJECT COORDINATES

LATITUDE: 34° 17' 32" N
LONGITUDE: 79° 52' 15" W


| | | | |
|------------------|-------|---|-------------------------------|
| DRAWN: CWS | SEAL: | COA:  | SHEET NO. C0.0 |
| CHECKED: DKB | | | |
| APPROVED: DKB | | | PROJECT NO. 1822005 |



**PRELIMINARY
NOT FOR CONSTRUCTION**



**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information

| No. | Name | Date |
|-----|------|------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Drawing Information


| | |
|-------------|----------|
| Project No. | 1822015 |
| Drawn By | OWS |
| Date | 03.24.23 |
| Checked By | DMB |
| Drawn By | OWS |
| Approved By | DMB |

**EXISTING
CONDITIONS
PLAN**

Drawing No.
C1.1



**PRELIMINARY
NOT FOR CONSTRUCTION**



Project Title / Client Information

**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | OWS |
| Checked By | DKB |
| Approved By | DKB |
| Date | 09.24.23 |
| Date | 09.24.23 |
| Date | 09.24.23 |

**STORM
DRAINAGE
PLAN**

Drawing No. **C2.1**

CONDUIT TABLE

| |
|--|
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |

JUNCTION TABLE

| |
|--|
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |

SEQUENCE OF CONSTRUCTION

- ITEMS MUST OCCUR IN THE ORDER LISTED; ITEMS CANNOT OCCUR CONCURRENTLY UNTIL SPECIFICALLY NOTED.
1. RECEIVE NPDES COVERAGE FROM SCDHEC.
 2. PRE-CONSTRUCTION MEETING WITH DARLINGTON COUNTY STORMWATER MANAGEMENT STAFF PRESENT.
 3. THE PROJECT IS A LINEAR DITCH IMPROVEMENT, CLEANING AND REGRADING OF DITCHES, AND INSTALLATION OF STORM DRAINAGE AND BOXES. AS SUCH, THE CONTRACTOR SHALL SCHEDULE HIS WORK TO COMPLETE IN SECTIONS. IT IS NOT INTENDED FOR THE ENTIRE PROJECT TO BE DISTURBED AT ONE TIME.
 4. LIMIT WORK BETWEEN ROADS CROSSINGS COMPLETING EACH CLEANING AND REGRADING BETWEEN ROADS COMPLETELY INCLUDING STABILIZATION BEFORE PROCEEDING TO THE NEXT AREA.
 5. DISTURBANCE SHOULD BE GENERALLY LIMITED TO 1,000 LF MAX WITH EROSION CONTROL AS "ROLLING" WITH THE PROJECT.
 6. ALL EXISTING INLETS SHALL BE PROTECTED BY SEDIMENT TUBES AS DETAILED IN THESE PLANS.
 7. ALL NEW INLETS SHALL BE PROTECTED BY SEDIMENT TUBE PLACED IN A CIRCULAR FASHION AS DETAILED IN THESE PLANS.
 8. NOTIFY DARLINGTON COUNTY STORMWATER MANAGEMENT STAFF 48 HOURS PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES.
 9. INSTALLATION OF CONSTRUCTION ENTRANCES.
 10. CLEARING AND GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS.
 11. INSTALLATION OF PERIMETER CONTROLS (E.G. SILT FENCE).
 12. CLEARING AND GRUBBING OF SITE AND TREE REMOVAL. (SEDIMENT AND EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED).
 13. TOP SOIL REMOVAL AND STOCKPILE WITH SILT FENCE AROUND PERIMETER.
 14. CLEANING AND CLEARING OF CHANNELS INDICATED ON THE PLANS.
 15. INSTALLATION OF CHECK DAMS IN CHANNEL.
 16. REMOVAL OF TREES, DEBRIS, AND OTHER ITEMS FROM CHANNEL.
 17. REGRADING DITCHES IN THE AREAS SHOWN IN THE PLANS.
 18. EXCAVATION OF OVBANK PER GRADING PLAN.
 19. INSTALL NEW STORM PIPING AND BOXES.
 20. INSTALL ENKAMAT BANK STABILIZATION AND/OR FLEXTERA AND/OR HYDROSEEDING.
 21. PERMANENT/FINAL STABILIZATION TO OTHER AREAS DISTURBED.
 22. REMOVAL OF TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED (THE DEPARTMENT RECOMMENDS THAT THE PROJECT OWNER/OPERATOR HAVE THE SWPPP PREPARER OR REGISTRATION EQUIVALENT APPROVE THE REMOVAL OF TEMPORARY STRUCTURES.)
 23. PREPARE A DETAILED AS-BUILT SURVEY OF THE STRUCTURES AND GRADED AREAS FOR SUBMITTAL TO THE CITY, SCDHEC, AND FEMA.

ONCE CONSTRUCTION IS COMPLETE THE ITEMS BELOW MUST BE PERFORMED IN THE ORDER SHOWN.

24. SUBMIT NOTICE OF TERMINATION (NOT) TO DARLINGTON COUNTY AND SCDHEC. MANAGEMENT STAFF.
- NOTE: MAINTENANCE OF SEDIMENT AND EROSION CONTROL MEASURES MUST CONTINUE UNTIL THE SITE IS PERMANENTLY STABILIZED AND THE CONTROLS ARE REMOVED.

CONTRACTOR NOTES

1. PRIOR TO BEGINNING CONSTRUCTION, THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED FROM ALL REGULATORY AUTHORITIES.
2. CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY TRENCHING OR EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. FOR ASSISTANCE WITH FIELD LOCATION OF EXISTING UTILITIES THE CONTRACTOR CAN CONTACT PUPS AT 1-888-721-7877.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL ILLUSTRATED KNOWN UNDERGROUND ELEMENTS. ADDITIONALLY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXERCISING REASONABLE EFFORT TO PROTECT ANY UNKNOWN UNDERGROUND ELEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF UNKNOWN ELEMENTS ARE DISCOVERED THAT WOULD NECESSITATE MODIFICATION TO THE ILLUSTRATED DESIGN.
5. THE CONTRACTOR SHALL PROTECT ALL ADJACENT PROPERTIES, THE GENERAL PUBLIC, AND ALL OTHER FACILITIES. SHOULD DAMAGES OCCUR, CONTRACTOR SHALL REPAIR IMMEDIATELY AS DIRECTED BY THE MANAGER/OWNER. CONTRACTOR IS FINANCIALLY RESPONSIBLE FOR ALL REPAIRS, AND REPAIRS ARE TO BE PERFORMED TO THE DEVELOPER'S APPROVAL.
6. THE CONTRACTOR SHALL UTILIZE SIGNS, BARRICADES, FLAGMEN, OR GUARDS AS REQUIRED TO ENSURE THE SAFETY OF ALL VEHICULAR AND PEDESTRIAN TRAFFIC DURING ALL CONSTRUCTION ACTIVITIES.
7. ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
8. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.
9. THE GENERAL CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND RIGHT-OF-WAYS, PUBLIC OR PRIVATE, PRIOR TO WORKING IN THESE AREAS.
10. CONTRACTOR TO BE RESPONSIBLE FOR SECURING THE SITE PRIOR TO SUBSTANTIAL COMPLETION OF THE PROJECT. REPAIRS, RESULTING FROM VANDALISM, TO BE AT HIS OWN EXPENSE.

EROSION CONTROL NOTES

1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO GRASSING/HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
 - » WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - » WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION, IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE IS STABILIZED.
6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ AND SCR100000.
8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
9. ALL WATERS OF THE STATE (WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10-FT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.
10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
11. A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT THE FINAL STABILIZATION IS REACHED.
12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF SEVEN (7) CALENDAR DAYS.
13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE Routed THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
 - » WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL
 - » WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FROM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS
 - » FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE
 - » SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING
17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
18. IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB MORE THAN 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.
20. SILT FENCING LINE ON EROSION CONTROL PLAN SHEETS ARE SHOWN FOR GRAPHICAL PURPOSES. SILT FENCING SHALL BE PLACED AT THE LIMITS OF DISTURBANCE

**PRELIMINARY
NOT FOR CONSTRUCTION**

PALMETTO UTILITY PROTECTION SERVICE




Don't Dig! Before you call
 toll free 1-888-721-7877

A one call system for community and job safety.



E.L. ROBINSON
ENGINEERING

1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



SOUTH CAROLINA
E.L. ROBINSON
Engineer
No. 75544
CERTIFICATE OF

**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information

| | | | | |
|------|--|--|--|--|
| Date | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |





Drawing Information

| | | | | |
|---------------------|--|--|--|--|
| Project No. 1822005 | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**STORM DRAINAGE
TABLES AND NOTES**

Drawing No.


C2.2



**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|-----------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| - - - - - | 10-YEAR FLOODPLAIN |
| ——— | TOP OF PIPE/CHANNEL |
| ————— | BOTTOM OF PIPE/CHANNEL |

**E.L. ROBINSON
ENGINEERING**
 1301 Cervais St., Suite 450
 Columbia, SC 29201
 Phone: (803) 400-6031
 www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**
 SOUTH CAROLINA OFFICE OF RESILIENCE
 DARLINGTON COUNTY, SOUTH CAROLINA





| Revisions | Proj. No. | Date |
|-----------|-----------|------|
| | 1822005 | |

| Rev. | Name |
|------|------|
| | |

| Drawing Information | |
|---------------------|----------|
| Project No. | 1822005 |
| Drawn By | OWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |


**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.1



**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|--------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| ----- | 10-YEAR FLOODPLAIN |
| ————— | TOP OF PIPE/CHANNEL |
| ————— | BOTTOM OF PIPE/CHANNEL |



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA





Project Title / Client Information

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|---------------------|----------|
| Drawing Information | |
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**


Drawing No.
C3.2



LEGEND

- 2-YEAR FLOODPLAIN
- 10-YEAR FLOODPLAIN
- TOP OF PIPE/CHANNEL
- BOTTOM OF PIPE/CHANNEL

**PRELIMINARY
NOT FOR CONSTRUCTION**



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information





| No. | Name | Date |
|-----|------|------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Drawing Information

| | |
|-------------|----------|
| Project No. | 1822015 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.3




LEGEND

- 2-YEAR FLOODPLAIN
- 10-YEAR FLOODPLAIN
- TOP OF PIPE/CHANNEL
- BOTTOM OF PIPE/CHANNEL

**PRELIMINARY
NOT FOR CONSTRUCTION**

**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

Project Title / Client Information


| No. | Name | Date |
|-----|------|------|
| | | |
| | | |
| | | |
| | | |

Drawing Information

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Drawn Date | 03.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.4




**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|--------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| ----- | 10-YEAR FLOODPLAIN |
| ----- | TOP OF PIPE/CHANNEL |
| ----- | BOTTOM OF PIPE/CHANNEL |



**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



**DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS**


SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Project Title / Client Information | |
|------------------------------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Approved By | DKB |
| Date | 03.24.23 |

| Drawing Information | |
|---------------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DKB |
| Approved By | DKB |
| Date | 03.24.23 |

**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.5



SUGGESTED CONSTRUCTION SEQUENCING (note to designer: edit as needed to meet project requirements)


1. Install appropriate temporary erosion control devices to prevent sediment from leaving or entering the practice during construction.
2. All down-gradient perimeter sediment control BMP's must be in place before any up gradient land disturbing activity begins.
3. Perform continuous inspections of erosion control practices, especially after each rainfall event.
4. Install all utilities (water, sanitary sewer, electric, natural gas, phone, fiber optic, etc) prior to setting final grade of bio-retention device.
5. Rough grade the site. If bio-retention areas are being used as temporary sediment basins during construction, leave a minimum of 1 foot of cover over the practice to protect the underlying soils from clogging.
6. Complete, stabilize, and vegetate all other site improvements.
7. Construct and vegetate bio-retention device following stabilization of contributing drainage area. Ensure that critical elevations, such as underdrain invert, top of media, top of mulch, and invert of overflow structure (if present) are correct.
8. Remove temporary erosion control devices after the contributing drainage area is adequately vegetated.

GENERAL NOTES (note to designer: edit as needed to meet project requirements)

1. In the event that sediment is introduced into the bmp during or immediately following excavation, this material shall be removed from the practice prior to continuing construction.
2. See SCDHEC Stormwater Manual for subgrade preparation.

MATERIAL SPECIFICATIONS

1. See SCDHEC Stormwater Manual for material specifications recommendations for bio-retention soil, mulch, underdrains, etc.



WHEN AND WHERE TO USE IT
 SILT FENCE IS APPLICABLE IN AREAS:
 WHERE THE MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE FENCE IS 100- FEET.
 WHERE THE MAXIMUM SLOPE STEEPNESS (NORMAL PERPENDICULAR TO FENCE LINE) IS 2H:1V.
 THAT DO NOT RECEIVE CONCENTRATED FLOWS GREATER THAN 0.5 CFS.

DO NOT PLACE SILT FENCE ACROSS CHANNELS OR USE IT AS A VELOCITY CONTROL BMP.

MATERIALS

STEEL POSTS
 USE 48-INCH LONG STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS:
 COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI.
 HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T"
 LENGTH OF 1.48-INCHES.
 WEIGH 1.25 POUNDS PER FOOT (± 8%).
 HAVE A SOIL STABILIZATION PLATE WITH A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES
 ATTACHED TO THE STEEL POSTS.
 PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

USE STEEL POSTS WITH A MINIMUM LENGTH OF 4- FEET, WEIGHING 1.25 POUNDS PER LINEAR FOOT (± 8%) WITH PROJECTIONS TO AID IN FASTENING THE FABRIC. EXCEPT WHEN HEAVY CLAY SOILS ARE PRESENT ON SITE, STEEL POSTS WILL HAVE A METAL SOIL STABILIZATION PLATE WELDED NEAR THE BOTTOM SUCH THAT WHEN THE POST IS DRIVEN TO THE PROPER DEPTH, THE PLATE WILL BE BELOW THE GROUND LEVEL FOR ADDED STABILITY. THE SOIL PLATES SHOULD HAVE THE FOLLOWING CHARACTERISTICS:
 BE COMPOSED OF MINIMUM 15 GAUGE STEEL.
 HAVE A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES.


GEOTEXTILE FILTER FABRIC

FILTER FABRIC IS:
 COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS COMPOSED OF AT LEAST 85% BY WEIGHT OF POLYPROPYLENE, POLYESTERS, OR POLYAMIDES. FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE TO EACH OTHER. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER INSTALLATION. FREE OF DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES. CUT TO A MINIMUM WIDTH OF 36 INCHES.

USE ONLY FABRIC APPEARING ON SCOOT APPROVAL SHEET #34 MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SCOOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

INSTALLATION:
 EXCAVATE A TRENCH APPROXIMATELY 6-INCHES WIDE AND 6-INCHES DEEP WHEN PLACING FABRIC BY HAND. PLACE 12-INCHES OF GEOTEXTILE FABRIC INTO THE 6-INCH DEEP TRENCH, EXTENDING THE REMAINING 6-INCHES TOWARDS THE UPSLOPE SIDE OF THE TRENCH. BACKFILL THE TRENCH WITH SOIL OR GRAVEL AND COMPACT. BURY 12-INCHES OF FABRIC INTO THE GROUND WHEN PNEUMATICALLY INSTALLING SILT FENCE WITH A SLICING METHOD. PURCHASE FABRIC IN CONTINUOUS ROLLS AND CUT TO LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, WRAP THE FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST. INSTALL THE FABRIC A MINIMUM OF 24-INCHES OVERLAP. INSTALL POSTS TO A MINIMUM DEPTH OF 24-INCHES. INSTALL POSTS A MINIMUM OF 1- TO 2-INCHES ABOVE THE FABRIC, WITH NO MORE THAN 3- FEET OF THE POST ABOVE THE GROUND. SPACE POSTS TO MAXIMUM 6- FEET CENTERS. ATTACH FABRIC TO WOOD POSTS USING STAPLES MADE OF HEAVY DUTY WIRE AT LEAST 1 1/2-INCH LONG, SPACED A MAXIMUM OF 6-INCHES APART. STAPLE A 2-INCH WIDE LATHE OVER THE FILTER FABRIC TO SECURELY FASTEN IT TO THE UPSLOPE SIDE OF WOODEN POSTS. ATTACH FABRIC TO THE STEEL POSTS USING HEAVY DUTY PLASTIC TIES THAT ARE EVENLY SPACED AND PLACED IN A MANNER TO PREVENT SAGGING OR TEARING OF THE FABRIC. IN ALL CASES, TIES SHOULD BE AFFIXED IN NO LESS THAN 4 PLACES. INSTALL THE FABRIC A MINIMUM OF 24-INCHES ABOVE THE GROUND. WHEN NECESSARY, THE HEIGHT OF THE FENCE ABOVE GROUND MAY BE GREATER THAN 24-INCHES. IN TIDAL AREAS, EXTRA SILT FENCE HEIGHT MAY BE REQUIRED. THE POST HEIGHT WILL BE TWICE THE EXPOSED POST HEIGHT. POST SPACING WILL REMAIN THE SAME AND EXTRA HEIGHT FABRIC WILL BE 4-, 5-, OR 6- FEET TALL. LOCATE SILT FENCE CHECKS EVERY 100 FEET MAXIMUM AND AT LOW POINTS. INSTALL THE FENCE PERPENDICULAR TO THE DIRECTION OF FLOW AND PLACE THE FENCE THE DISTANCE FROM THE TOE OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR MAINTENANCE AND CLEANOUT.




INSPECTION AND MAINTENANCE:
 INSPECT EVERY SEVEN CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION. CHECK FOR SEDIMENT BUILDUP AND FENCE INTEGRITY. CHECK WHERE RUNOFF HAS ERODED A CHANNEL BENEATH THE FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED BY FENCE OVERTOPPING. IF THE FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE SECTION OF FENCE IMMEDIATELY. REMOVE SEDIMENT ACCUMULATED ALONG THE FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE, ESPECIALLY IF HEAVY RAINS ARE EXPECTED. REMOVE TRAPPED SEDIMENT FROM THE SITE OR STABILIZE IT ON SITE. REMOVE SILT FENCE WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED OR AFTER TEMPORARY BEST MANAGEMENT PRACTICES (BMPs) ARE NO LONGER NEEDED. PERMANENTLY STABILIZE DISTURBED AREAS RESULTING FROM FENCE REMOVAL.



SUGGESTED CONSTRUCTION SEQUENCING (note to designer: edit as needed to meet project requirements)

1. If NECESSARY, SLOPES, WHICH EXCEED (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW:
 a. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS, STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 b. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH DISTURBING ACTIVITIES WILL BE RESUMED WITHIN FOURTEEN (14) DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY SEVEN (7) DAYS. IF SITE INSPECTIONS IDENTIFY BMPs THAT ARE DAMAGED AND/OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE AND BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE.
 OR
 ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AT LEAST ONCE EVERY FOURTEEN (14) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. IF SITE INSPECTIONS IDENTIFY BMPs THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE AND BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE.
4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
6. THE GENERAL CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE GENERAL CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 et seq. AND SCR1000000.
8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOs. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOs.
10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

SEDIMENT AND EROSION CONTROL NOTES



WHEN AND WHERE TO USE IT
 STABILIZED CONSTRUCTION ENTRANCES SHOULD BE USED AT ALL POINTS WHERE TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE AND MOVING DIRECTLY ONTO A PUBLIC ROAD.

IMPORTANT CONSIDERATIONS:
 IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFFSITE. WASHDOWN FACILITIES SHALL BE REQUIRED AS DIRECTED BY SCDHEC AS NEEDED. WASHDOWN AREAS IN GENERAL MUST BE ESTABLISHED WITH CRUSHED GRAVEL AND DRAIN INTO A SEDIMENT TRAP OR SEDIMENT BASIN. CONSTRUCTION ENTRANCES SHOULD BE USED IN CONJUNCTION WITH THE STABILIZATION OF CONSTRUCTION ROADS TO REDUCE THE AMOUNT OF MUD PICKED UP BY VEHICLES.

INSTALLATION:
 REMOVE ALL VEGETATION AND ANY OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA.
 DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM STONES TO A SEDIMENT TRAP OR BASIN.
 INSTALL A NON-WOVEN GEOTEXTILE FABRIC PRIOR TO PLACING ANY STONE.
 INSTALL A CULVERT PIPE ACROSS THE ENTRANCE WHEN NEEDED TO PROVIDE POSITIVE DRAINAGE.
 THE ENTRANCE SHALL CONSIST OF 1-INCH TO 3-INCH D50 STONE PLACED AT A MINIMUM DEPTH OF 6-INCHES.
 MINIMUM DIMENSIONS OF THE ENTRANCE SHALL BE 24- FEET WIDE BY 100- FEET LONG, AND MAY BE MODIFIED AS NECESSARY TO ACCOMMODATE SITE CONSTRAINTS.
 THE EDGES OF THE ENTRANCE SHALL BE TAPERED OUT TOWARDS THE ROAD TO PREVENT TRACKING OF MUD AT THE EDGE OF THE ENTRANCE.

INSPECTION AND MAINTENANCE:
 INSPECT CONSTRUCTION ENTRANCES EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION, OR AFTER HEAVY USE. CHECK FOR MUD AND SEDIMENT BUILDUP AND PAD INTEGRITY. MAKE DAILY INSPECTIONS DURING PERIODS OF WET WEATHER. MAINTENANCE IS REQUIRED MORE FREQUENTLY IN WET WEATHER CONDITIONS. RESHAPE THE STONE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
 WASH OR REPLACE STONES AS NEEDED AND AS DIRECTED BY THE INSPECTOR. THE STONE IN THE ENTRANCE SHOULD BE WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFF-SITE BY VEHICLES. FREQUENT WASHING WILL EXTEND THE USEFUL LIFE OF STONE.
 IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED WHEN THE WATER CAN BE DISCHARGED TO A SEDIMENT TRAP OR BASIN.
 REPAIR ANY BROKEN PAVEMENT IMMEDIATELY.

SEEDING SCHEDULE FOR TEMPORARY VEGETATION UPPER AND LOWER STATE

| SCHEDULE NO. | COMMON NAME OF SEED | RATE PER ACRE (LBS.) | PLANTING DATES |
|--------------|------------------------------------|----------------------|-----------------------|
| 1 | ANNUAL SUDAN GRASS (SWEET OR TIFF) | 40 | APRIL 1 TO AUGUST 15 |
| 2 | BROWN TOP MILLET | 50 | APRIL 1 TO AUGUST 15 |
| 3 | RYE GRAIN | 55 | AUGUST 16 TO MARCH 31 |

SEEDING SCHEDULE FOR PERMANENT VEGETATION

| SCHEDULE NO. | COMMON NAME OF SEED | RURAL RATE | URBAN RATE | PLANTING DATES |
|--------------|----------------------------|------------|------------|--------------------------|
| 3' | COMMON BERMUDA (HULLED*) | 20 | 20 | MARCH 1 TO AUGUST 14 |
| | CARPET GRASS | 9 | 9 | |
| 4' | COMMON BERMUDA (UNHULLED*) | 20 | 20 | AUGUST 15 TO FEBRUARY 28 |
| | RYE GRAIN | 20 | 20 | |

- NOTES:**
1. INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
 2. NOT REQUIRED ON SHOULDERS, MEDIANS, ETC., AND SLOPES UNDER 5 FEET IN HEIGHT.
 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.

SEEDING SCHEDULE


**PRELIMINARY
 NOT FOR CONSTRUCTION**

| Date | Revisions |
|------|-----------|
| | |
| | |
| | |
| | |
| | |

| Project Title / Client Information | | | |
|------------------------------------|----------|-------------|----------|
| Project No. | 1822005 | Revision | No. |
| Drawn by | 03.24.23 | Checked by | 03.24.23 |
| Date | | DWG | |
| | | Approved by | |
| | | DWG | |

DETAILS


Drawing No. **C4.1**



CUDO Stormwater Products, Inc.
 P.O. Box 497 Occidental, CA 95465
 Ph. (877) 876-3345 Fax (707) 876-3346

CUDO Stormwater Detention System
 Typical Installation Detail
 Permeable Pavement Area



DD NOT SCALE DRAWING NONE JPR 7/21/08 0001 JPR 10/22/08 REV. A SHEET 1 OF 1



CUDO Stormwater Products, Inc.
 P.O. Box 497 Occidental, CA 95465
 Ph. (877) 876-3345 Fax (707) 876-3346

CUDO Water Storage System
 Typical System Layout
 w/ Filter Module Stacks.

DRAWING NO. CUDO-0007 REV. A 0001 JPR 9/26/08 DATE JPR 5/2/08 SHEET 1 OF 1



PRELIMINARY
NOT FOR CONSTRUCTION

E.L. ROBINSON ENGINEERING
 1301 Gervais St., Suite 450
 Columbia, SC 29201
 Phone: (803) 400-6031
 www.elrobinsonengineering.com

CERTIFIED PROFESSIONAL ENGINEER
 No. 2544


DARLINGTON COUNTY
H&H STUDY - CHESTNUT ST.
PROPOSED CONDITIONS
 SOUTH CAROLINA OFFICE OF RESILIENCE
 DARLINGTON COUNTY, SOUTH CAROLINA

| | | |
|------------------------------------|-------------|----------|
| Project Title / Client Information | Project No. | 1822005 |
| Design Information | Scale | AS SHOWN |
| Drawn By | Checked By | DATE |
| DATE | DATE | DATE |
| DATE | DATE | DATE |
| DATE | DATE | DATE |
| DATE | DATE | DATE |
| DATE | DATE | DATE |


DETAILS

Drawing No. **C4.2**

DARLINGTON COUNTY H&H STUDY PROPOSED CONDITIONS - MLK DR. FOR SOUTH CAROLINA OFFICE OF RESILIENCE



SITE MAP
SCALE: 1"=5,000'



LOCATION MAP

SCOR PROJECT NUMBER PP-21-1600-01
ELR PROJECT NUMBER 1822005

10% PLANS SUBMITTAL

MARCH 24, 2023

**PRELIMINARY
NOT FOR CONSTRUCTION**

The Palmetto Utility Protection Service, Inc.
810 Dutch Square Boulevard, Suite 220 Columbia, South Carolina 29210 Voice (803) 939-1117 Fax (803) 939-0704



3 DAYS BEFORE DICING IN
SOUTH CAROLINA
CALL 1-888-721-7877

UNDERGROUND LOCATORS.
CONTRACTOR SHALL CONTACT
THE UNDERGROUND LOCATORS
EVERY 10 DAYS FOR AN UPDATE
TO UTILITY LOCATIONS.

Call BEFORE you DIG!

DRAWING INDEX

CIVIL

| | |
|-----------|---------------------------------|
| C0.0 | COVER SHEET |
| C1.1 | EXISTING CONDITIONS |
| C2.1 | STORM DRAINAGE PLAN |
| C2.2 | STORM DRAINAGE TABLES AND NOTES |
| C3.1 | STORM DRAINAGE PROFILES |
| C4.1-C4.2 | DETAILS |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

SOUTH CAROLINA OFFICE OF RESILIENCE

ATTN: PHLEISHA LEWIS
632 ROSEWOOD DRIVE
COLUMBIA, SC 29201
PHLEISHA.LEWIS@SCOR.SC.GOV
Phone: (803) 543-0018




**E.L. ROBINSON
ENGINEERING**

1301 Gervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com


PROJECT COORDINATES

LATITUDE: 34° 21' 10" N
LONGITUDE: 80° 04' 39" W

| | | | |
|------------------|-------|---|-------------------------------|
| DRAWN: CWS | SEAL: | COA:  | SHEET NO. C0.0 |
| CHECKED: DKB | | | |
| APPROVED: DKB | | | PROJECT NO. 1822005 |



**PRELIMINARY
NOT FOR CONSTRUCTION**



**DARLINGTON COUNTY
H&H STUDY - MLK DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |


| | |
|---------------------|----------|
| Drawing Information | |
| Project No. | 1822015 |
| Drawn By | CWS |
| Date | 03.24.23 |
| Checked By | DHB |
| Drawn Date | 03.24.23 |
| Approved By | DHB |

**EXISTING
CONDITIONS
PLAN**

Drawing No. **C1.1**



**PRELIMINARY
NOT FOR CONSTRUCTION**



**DARLINGTON COUNTY
H&H STUDY - MLK DR.
PROPOSED CONDITIONS**
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |
| | | | |

| | |
|-------------|----------|
| Project No. | 1822015 |
| Drawn By | OWS |
| Date | 03.24.23 |
| Checked By | DBR |
| Drawn Date | 03.24.23 |
| Approved By | DBR |

**STORM
DRAINAGE
PLAN**

Drawing No. **C2.1**

CONDUIT TABLE

| |
|--|
| |
|--|

JUNCTION TABLE

| |
|--|
| |
|--|

SEQUENCE OF CONSTRUCTION

- ITEMS MUST OCCUR IN THE ORDER LISTED; ITEMS CANNOT OCCUR CONCURRENTLY UNTIL SPECIFICALLY NOTED.
1. RECEIVE NPDES COVERAGE FROM SCDHEC.
 2. PRE-CONSTRUCTION MEETING WITH CHESTERFIELD COUNTY STORMWATER MANAGEMENT STAFF PRESENT.
 3. THE PROJECT IS A LINEAR DITCH IMPROVEMENT, CLEANING AND REGRADING OF DITCHES, AND INSTALLATION OF STORM DRAINAGE AND BOXES. AS SUCH, THE CONTRACTOR SHALL SCHEDULE HIS WORK TO COMPLETE IN SECTIONS. IT IS NOT INTENDED FOR THE ENTIRE PROJECT TO BE DISTURBED AT ONE TIME.
 4. LIMIT WORK BETWEEN ROADS CROSSINGS COMPLETING EACH CLEANING AND REGRADING BETWEEN ROADS COMPLETELY INCLUDING STABILIZATION BEFORE PROCEEDING TO THE NEXT AREA.
 5. DISTURBANCE SHOULD BE GENERALLY LIMITED TO 1,000 LF MAX WITH EROSION CONTROL AS "ROLLING" WITH THE PROJECT.
 6. ALL EXISTING INLETS SHALL BE PROTECTED BY SEDIMENT TUBES AS DETAILED IN THESE PLANS.
 7. ALL NEW INLETS SHALL BE PROTECTED BY SEDIMENT TUBE PLACED IN A CIRCULAR FASHION AS DETAILED IN THESE PLANS.
 8. NOTIFY chesterfield county STORMWATER MANAGEMENT STAFF 48 HOURS PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES.
 9. INSTALLATION OF CONSTRUCTION ENTRANCES.
 10. CLEARING AND GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS.
 11. INSTALLATION OF PERIMETER CONTROLS (E.G. SILT FENCE).
 12. CLEARING AND GRUBBING OF SITE AND TREE REMOVAL. (SEDIMENT AND EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED).
 13. TOP SOIL REMOVAL AND STOCKPILE WITH SILT FENCE AROUND PERIMETER.
 14. CLEANING AND CLEARING OF CHANNELS INDICATED ON THE PLANS..
 15. INSTALLATION OF CHECK DAMS IN CHANNEL.
 16. REMOVAL OF TREES, DEBRIS, AND OTHER ITEMS FROM CHANNEL.
 17. REGRADING DITCHES IN THE AREAS SHOWN IN THE PLANS..
 18. EXCAVATION OF OVBANK PER GRADING PLAN.
 19. INSTALL NEW STORM PIPING AND BOXES.
 20. INSTALL ENKAMAT BANK STABILIZATION AND/OR FLEXTERRA AND/OR HYDROSEEDING.
 21. PERMANENT/FINAL STABILIZATION TO OTHER AREAS DISTURBED..
 22. REMOVAL OF TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED (THE DEPARTMENT RECOMMENDS THAT THE PROJECT OWNER/OPERATOR HAVE THE SWPPP PREPARER OR REGISTRATION EQUIVALENT APPROVE THE REMOVAL OF TEMPORARY STRUCTURES.)
 23. PREPARE A DETAILED AS-BUILT SURVEY OF THE STRUCTURES AND GRADED AREAS FOR SUBMITTAL TO THE CITY, SCDHEC, AND FEMA.

ONCE CONSTRUCTION IS COMPLETE THE ITEMS BELOW MUST BE PERFORMED IN THE ORDER SHOWN.

24. SUBMIT NOTICE OF TERMINATION (NOT) TO CHESTERFIELD COUNTY AND SCDHEC. MANAGEMENT STAFF.

- NOTE: MAINTENANCE OF SEDIMENT AND EROSION CONTROL MEASURES MUST CONTINUE UNTIL THE SITE IS PERMANENTLY STABILIZED AND THE CONTROLS ARE REMOVED.

CONTRACTOR NOTES

1. PRIOR TO BEGINNING CONSTRUCTION, THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED FROM ALL REGULATORY AUTHORITIES.
2. CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY TRENCHING OR EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. FOR ASSISTANCE WITH FIELD LOCATION OF EXISTING UTILITIES THE CONTRACTOR CAN CONTACT PUPS AT 1-888-721-7877.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL ILLUSTRATED KNOWN UNDERGROUND ELEMENTS. ADDITIONALLY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXERCISING REASONABLE EFFORT TO PROTECT ANY UNKNOWN UNDERGROUND ELEMENTS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IF UNKNOWN ELEMENTS ARE DISCOVERED THAT WOULD NECESSITATE MODIFICATION TO THE ILLUSTRATED DESIGN.
5. THE CONTRACTOR SHALL PROTECT ALL ADJACENT PROPERTIES, THE GENERAL PUBLIC, AND ALL OTHER FACILITIES. SHOULD DAMAGES OCCUR, CONTRACTOR SHALL REPAIR IMMEDIATELY AS DIRECTED BY THE MANAGER/OWNER. CONTRACTOR IS FINANCIALLY RESPONSIBLE FOR ALL REPAIRS, AND REPAIRS ARE TO BE PERFORMED TO THE DEVELOPER'S APPROVAL.
6. THE CONTRACTOR SHALL UTILIZE SIGNS, BARRICADES, FLAGMEN, OR GUARDS AS REQUIRED TO ENSURE THE SAFETY OF ALL VEHICULAR AND PEDESTRIAN TRAFFIC DURING ALL CONSTRUCTION ACTIVITIES.
7. ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
8. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.
9. THE GENERAL CONTRACTOR SHALL CONTACT ALL OWNERS OF EASEMENTS, UTILITIES AND RIGHT-OF-WAYS, PUBLIC OR PRIVATE, PRIOR TO WORKING IN THESE AREAS.
10. CONTRACTOR TO BE RESPONSIBLE FOR SECURING THE SITE PRIOR TO SUBSTANTIAL COMPLETION OF THE PROJECT. REPAIRS, RESULTING FROM VANDALISM, TO BE AT HIS OWN EXPENSE.

EROSION CONTROL NOTES

1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO GRASSING/HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED. EXCEPT AS STATED BELOW.
 - »WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - »WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION, IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE IS STABILIZED.
6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ AND SCR100000.
8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
9. ALL WATERS OF THE STATE (WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10-FT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.
10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
11. A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT THE FINAL STABILIZATION IS REACHED.
12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF SEVEN (7) CALENDAR DAYS.
13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
 - »WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL
 - »WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FROM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS
 - »FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE
 - »SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING
17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
18. IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB MORE THAN 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.
20. SILT FENCING LINE ON EROSION CONTROL PLAN SHEETS ARE SHOWN FOR GRAPHICAL PURPOSES. SILT FENCING SHALL BE PLACED AT THE LIMITS OF DISTURBANCE

**PRELIMINARY
NOT FOR CONSTRUCTION**

PALMETTO UTILITY PROTECTION SERVICE




Don't Dig! Before you call toll free 1-888-721-7877

A one call system for community and job safety.

**EL. ROBINSON
ENGINEERING**

1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com







**DARLINGTON COUNTY
H&H STUDY - MLK DR.
PROPOSED CONDITIONS**

SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | DB |
| Date | 03.24.23 |
| Checked By | DB |
| Date | 03.24.23 |
| Approved By | DB |

**STORM DRAINAGE
TABLES AND NOTES**


Drawing No. **C2.2**



**PRELIMINARY
NOT FOR CONSTRUCTION**

| LEGEND | |
|-----------|------------------------|
| ----- | 2-YEAR FLOODPLAIN |
| - - - - - | 10-YEAR FLOODPLAIN |
| ————— | TOP OF PIPE/CHANNEL |
| ————— | BOTTOM OF PIPE/CHANNEL |

**E.L. ROBINSON
ENGINEERING**
1301 Cervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



Project Title / Client Information

**DARLINGTON COUNTY
H&H STUDY - MLK DR.
PROPOSED CONDITIONS**


SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |

| | |
|-------------|----------|
| Project No. | 1822005 |
| Drawn By | CWS |
| Date | 09.24.23 |
| Checked By | DKB |
| Drawn Date | 09.24.23 |
| Approved By | DKB |

**STORM
DRAINAGE
PROFILES**

Drawing No.
C3.1



SILT FENCE INSTALLATION

WHEN AND WHERE TO USE IT
SILT FENCE IS APPLICABLE IN AREAS:
WHERE THE MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE FENCE IS 100- FEET.
WHERE THE MAXIMUM SLOPE STEEPNESS (NORMAL PERPENDICULAR TO FENCE LINE) IS 2H:1V.
THAT DO NOT RECEIVE CONCENTRATED FLOWS GREATER THAN 0.5 CFS.

DO NOT PLACE SILT FENCE ACROSS CHANNELS OR USE IT AS A VELOCITY CONTROL BMP.

MATERIALS

STEEL POSTS
USE 48-INCH LONG STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS:
COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI.
HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T" LENGTH OF 1.48-INCHES.
WEIGH 1.25 POUNDS PER FOOT (± 8%).
HAVE A SOIL STABILIZATION PLATE WITH A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES ATTACHED TO THE STEEL POSTS.
PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

USE STEEL POSTS WITH A MINIMUM LENGTH OF 4- FEET, WEIGHING 1.25 POUNDS PER LINEAR FOOT (± 8%) WITH PROJECTIONS TO AID IN FASTENING THE FABRIC. EXCEPT WHEN HEAVY CLAY SOILS ARE PRESENT ON SITE, STEEL POSTS WILL HAVE A METAL SOIL STABILIZATION PLATE WELDED NEAR THE BOTTOM SUCH THAT WHEN THE POST IS DRIVEN TO THE PROPER DEPTH, THE PLATE WILL BE BELOW THE GROUND LEVEL FOR ADDED STABILITY. THE SOIL PLATES SHOULD HAVE THE FOLLOWING CHARACTERISTICS:
BE COMPOSED OF MINIMUM 15 GAUGE STEEL.
HAVE A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES.

GEOTEXTILE FILTER FABRIC

FILTER FABRIC IS:
COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS COMPOSED OF AT LEAST 85% BY WEIGHT OF POLYPROPYLENE, POLYESTERS, OR POLYAMIDES. FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE TO EACH OTHER. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER INSTALLATION. FREE OF DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES. CUT TO A MINIMUM WIDTH OF 36 INCHES.

USE ONLY FABRIC APPEARING ON SCOOT APPROVAL SHEET #34 MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SCOOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

INSTALLATION:


EXCAVATE A TRENCH APPROXIMATELY 6-INCHES WIDE AND 6-INCHES DEEP WHEN PLACING FABRIC BY HAND. PLACE 12-INCHES OF GEOTEXTILE FABRIC INTO THE 6-INCH DEEP TRENCH, EXTENDING THE REMAINING 6-INCHES TOWARDS THE UPSLOPE SIDE OF THE TRENCH. BACKFILL THE TRENCH WITH SOIL OR GRAVEL AND COMPACT. BURY 12-INCHES OF FABRIC INTO THE GROUND WHEN PNEUMATICALLY INSTALLING SILT FENCE WITH A SLICING METHOD. PURCHASE FABRIC IN CONTINUOUS ROLLS AND CUT TO LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, WRAP THE FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST. INSTALL THE FABRIC A MINIMUM OF 24-INCHES OVERLAP. INSTALL POSTS TO A MINIMUM DEPTH OF 24-INCHES. INSTALL POSTS TO A MINIMUM OF 1- TO 2-INCHES ABOVE THE FABRIC, WITH NO MORE THAN 3- FEET OF THE POST ABOVE THE GROUND. SPACE POSTS TO MAXIMUM 6- FEET CENTERS. ATTACH FABRIC TO WOOD POSTS USING STAPLES MADE OF HEAVY DUTY WIRE AT LEAST 1 1/2-INCH LONG, SPACED A MAXIMUM OF 6-INCHES APART. STAPLE A 2-INCH WIDE LATHE OVER THE FILTER FABRIC TO SECURELY FASTEN IT TO THE UPSLOPE SIDE OF WOODEN POSTS. ATTACH FABRIC TO THE STEEL POSTS USING HEAVY DUTY PLASTIC TIES THAT ARE EVENLY SPACED AND PLACED IN A MANNER TO PREVENT SAGGING OR TEARING OF THE FABRIC. IN ALL CASES, TIES SHOULD BE FASTENED IN NO LESS THAN 4 PLACES. INSTALL THE FABRIC A MINIMUM OF 24-INCHES ABOVE THE GROUND. WHEN NECESSARY, THE HEIGHT OF THE FENCE ABOVE GROUND MAY BE GREATER THAN 24-INCHES. IN TIDAL AREAS, EXTRA SILT FENCE HEIGHT MAY BE REQUIRED. THE POST HEIGHT WILL BE TWICE THE EXPOSED POST HEIGHT. POST SPACING WILL REMAIN THE SAME AND EXTRA HEIGHT FABRIC WILL BE 4-, 5-, OR 6- FEET TALL. LOCATE SILT FENCE CHECKS EVERY 100 FEET MAXIMUM AND AT LOW POINTS. INSTALL THE FENCE PERPENDICULAR TO THE DIRECTION OF FLOW AND PLACE THE FENCE AT THE DISTANCE FROM THE TOE OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR MAINTENANCE AND CLEANOUT.

INSPECTION AND MAINTENANCE:

INSPECT EVERY SEVEN CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION. CHECK FOR SEDIMENT BUILDUP AND FENCE INTEGRITY. CHECK WHERE RUNOFF HAS ERODED A CHANNEL BENEATH THE FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED BY FENCE OVERTOPPING. IF THE FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE SECTION OF FENCE IMMEDIATELY. REMOVE SEDIMENT ACCUMULATED ALONG THE FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE, ESPECIALLY IF HEAVY RAINS ARE EXPECTED. REMOVE TRAPPED SEDIMENT FROM THE SITE OR STABILIZE IT ON SITE. REMOVE SILT FENCE WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED OR AFTER TEMPORARY BEST MANAGEMENT PRACTICES (BMPs) ARE NO LONGER NEEDED. PERMANENTLY STABILIZE DISTURBED AREAS RESULTING FROM FENCE REMOVAL.

SILT FENCE DETAIL
(NOT TO SCALE)


- SUGGESTED CONSTRUCTION SEQUENCING (note to designer: edit as needed to meet project requirements)**
1. Install appropriate temporary erosion control devices to prevent sediment from leaving or entering the practice during construction.
 2. All down-gradient perimeter sediment control BMPs must be in place before any up gradient land disturbing activity begins.
 3. Perform continuous inspections of erosion control practices, especially after each rainfall event.
 4. Install all utilities (water, sanitary sewer, electric, natural gas, phone, fiber optic, etc) prior to setting final grade of bioretention device.
 5. Rough grade the site. If bioretention areas are being used as temporary sediment basins during construction, leave a minimum of 1 foot of cover over the practice to protect the underlying soils from clogging.
 6. Complete, stabilize, and vegetate all other site improvements.
 7. Construct and vegetate bioretention device following stabilization of contributing drainage area. Ensure that critical elevations, such as underdrain invert, top of media, top of mulch, and invert of overflow structure (if present) are correct.
 8. Remove temporary erosion control devices after the contributing drainage area is adequately vegetated.
- GENERAL NOTES (note to designer: edit as needed to meet project requirements)**
1. In the event that sediment is introduced into the BMP during or immediately following excavation, this material shall be removed from the practice prior to continuing construction.
 2. See SCDHEC Stormwater Manual for subgrade preparation.
- MATERIAL SPECIFICATIONS**
1. See SCDHEC Stormwater Manual for material specifications recommendations for bioretention soil, mulch, underdrains, etc.




BIO-RETENTION AREA DETAIL
(NOT TO SCALE)

1. IF NECESSARY, SLOPES, WHICH EXCEED (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW:
 - a. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS, STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - b. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH DISTURBING ACTIVITIES WILL BE RESUMED WITHIN FOURTEEN (14) DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY SEVEN (7) DAYS. IF SITE INSPECTIONS IDENTIFY BMPs THAT ARE DAMAGED AND/OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE AND BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE.
- OR
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AT LEAST ONCE EVERY FOURTEEN (14) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. IF SITE INSPECTIONS IDENTIFY BMPs THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE AND BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE.
4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
6. THE GENERAL CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE GENERAL CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 et seq. AND SCR100000.
7. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
8. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
9. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.


SEDIMENT AND EROSION CONTROL NOTES



STABILIZED CONSTRUCTION ENTRANCE/EXIT
(NOT TO SCALE)



RCP PIPE BEDDING & BACKFILLING DETAIL
(NOT TO SCALE)



EROSION CONTROL MATTING
(NOT TO SCALE)

WHEN AND WHERE TO USE IT

STABILIZED CONSTRUCTION ENTRANCES SHOULD BE USED AT ALL POINTS WHERE TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE AND MOVING DIRECTLY ONTO A PUBLIC ROAD.

IMPORTANT CONSIDERATIONS:

IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFFSITE. WASHDOWN FACILITIES SHALL BE REQUIRED AS DIRECTED BY SCDHEC AS NEEDED. WASHDOWN AREAS IN GENERAL MUST BE ESTABLISHED WITH CRUSHED GRAVEL AND DRAIN INTO A SEDIMENT TRAP OR SEDIMENT BASIN. CONSTRUCTION ENTRANCES SHOULD BE USED IN CONJUNCTION WITH THE STABILIZATION OF CONSTRUCTION ROADS TO REDUCE THE AMOUNT OF MUD PICKED UP BY VEHICLES.

INSTALLATION:

REMOVE ALL VEGETATION AND ANY OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA.

DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM STONES TO A SEDIMENT TRAP OR BASIN.

INSTALL A NON-WOVEN GEOTEXTILE FABRIC PRIOR TO PLACING ANY STONE.

INSTALL A CULVERT PIPE ACROSS THE ENTRANCE WHEN NEEDED TO PROVIDE POSITIVE DRAINAGE.

THE ENTRANCE SHALL CONSIST OF 1-INCH TO 3-INCH D50 STONE PLACED AT A MINIMUM DEPTH OF 6-INCHES.

MINIMUM DIMENSIONS OF THE ENTRANCE SHALL BE 24- FEET WIDE BY 100- FEET LONG, AND MAY BE MODIFIED AS NECESSARY TO ACCOMMODATE SITE CONSTRAINTS.

THE EDGES OF THE ENTRANCE SHALL BE TAPERED OUT TOWARDS THE ROAD TO PREVENT TRACKING OF MUD AT THE EDGE OF THE ENTRANCE.

INSPECTION AND MAINTENANCE:

INSPECT CONSTRUCTION ENTRANCES EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION, OR AFTER HEAVY USE. CHECK FOR MUD AND SEDIMENT BUILDUP AND PAD INTEGRITY. MAKE DAILY INSPECTIONS DURING PERIODS OF WET WEATHER. MAINTENANCE IS REQUIRED MORE FREQUENTLY IN WET WEATHER CONDITIONS. RESHAPE THE STONE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.

WASH OR REPLACE STONES AS NEEDED AND AS DIRECTED BY THE INSPECTOR. THE STONE IN THE ENTRANCE SHOULD BE WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFF-SITE BY VEHICLES. FREQUENT WASHING WILL EXTEND THE USEFUL LIFE OF STONE.

IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED WHEN THE WATER CAN BE DISCHARGED TO A SEDIMENT TRAP OR BASIN.

REPAIR ANY BROKEN PAVEMENT IMMEDIATELY.

SEEDING SCHEDULE FOR TEMPORARY VEGETATION UPPER AND LOWER STATE

| SCHEDULE NO. | COMMON NAME OF SEED | RATE PER ACRE (LBS.) | PLANTING DATES |
|--------------|------------------------------------|----------------------|-----------------------|
| 1 | ANNUAL SUDAN GRASS (SWEET OR TIFF) | 40 | APRIL 1 TO AUGUST 15 |
| 2 | BROWN TOP MILLET | 50 | APRIL 1 TO AUGUST 15 |
| 3 | RYE GRAIN | 55 | AUGUST 16 TO MARCH 31 |


SEEDING SCHEDULE FOR PERMANENT VEGETATION

| SCHEDULE NO. | COMMON NAME OF SEED | RURAL RATE | URBAN RATE | PLANTING DATES |
|--------------|----------------------------|------------|------------|--------------------------|
| 3' | COMMON BERMUDA (HULLED*) | 20 | 20 | MARCH 1 TO AUGUST 14 |
| | CARPET GRASS | 9 | 9 | |
| 4' | COMMON BERMUDA (UNHULLED*) | 20 | 20 | AUGUST 15 TO FEBRUARY 28 |
| | RYE GRAIN | 20 | 20 | |

- NOTES:**
1. INCLUDES RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.
 2. NOT REQUIRED ON SHOULDERS, MEDIANS, ETC., AND SLOPES UNDER 5 FEET IN HEIGHT.
 3. GIANT BERMUDA SEED, INCLUDING NK-37, SHALL NOT BE USED.
 4. RESEEDING CRIMSON CLOVER SHALL BE INOCULATED IN ACCORDANCE WITH SUBSECTION 810.05. DO NOT PLANT CLOVER IN MEDIANS OR IN RURAL AREAS ADJACENT TO WELL-DEVELOPED LAWNS.





SEEDING SCHEDULE

PRELIMINARY
NOT FOR CONSTRUCTION



DARLINGTON COUNTY H&H STUDY - MLK DR. PROPOSED CONDITIONS

| Date | Revisions | Project Title / Client Information |
|------|-----------|---|
| | | DARLINGTON COUNTY H&H STUDY - MLK DR. PROPOSED CONDITIONS |
| | | SOUTH CAROLINA OFFICE OF RESILIENCE DARLINGTON COUNTY, SOUTH CAROLINA |



E.L. ROBINSON
ENGINEERING
1301 Gervais St., Suite 450
Columbia, SC 29201
Phone: (803) 400-6031
www.elrobinsonengineering.com



NO. 2544
E.L. ROBINSON
ENGINEER
COLUMBIA, SC

DARLINGTON COUNTY
H&H STUDY - MLK DR.
PROPOSED CONDITIONS
SOUTH CAROLINA OFFICE OF RESILIENCE
DARLINGTON COUNTY, SOUTH CAROLINA

| Revisions | No. | Name | Date |
|-----------|-----|------|------|
| | | | |
| | | | |
| | | | |

| Drawing Information | |
|---------------------|--|
| Project No. 1822005 | |
| Drawn by CWS | |
| Date 03.24.23 | |
| Checked by DNB | |
| Date 03.24.23 | |
| Approved by DNB | |

DETAILS

PRELIMINARY
NOT FOR CONSTRUCTION

Drawing No. **C4.2**